THE PENNSYLVANIA STATE UNIVERSITY
SCHREYER HONORS COLLEGE

DEPARTMENT OF ARCHITECTURAL ENGINEERING

PEARLAND RECREATION CENTER AND NATATORIUM

MATT SMIDDY
Spring 2010

A thesis
submitted in partial fulfillment
of the requirements
for baccalaureate degrees
in Architectural Engineering and Economics
with honors in Architectural Engineering

Reviewed and approved* by the following:

Kevin Parfitt
Associate Professor of Architectural Engineering
Thesis Supervisor

Dr. David Riley
Associate Professor of Architectural Engineering
Honors Adviser

* Signatures are on file in the Schreyer Honors College.

Abstract

Pearland Recreation Center and Natatorium

Pearland, Texas

Project Overview:

Use: Community Recreation Center
Size: 105,000 SF of Floor Space
Height: 2 Stories
Construction Dates: May 2009 - June 2010
Construction Cost: ~$17 Million
Delivery Method: Design-Bid Build
Competitive Bid
Lump Sum



Mechanical:

- Three (3) 2000-5000 CFM Outside AHUs
- Eight (8) 3000-19000 CFM Inside AHUs
- Two (2) 1,063,000 BTUH Natrual Gas Boilers
- Two (2) 1,699,000 BTUH Natural Gas Boilers
- Two (2) 138 Ton Chillers
- Seven (7) 100-340 GPM Pumps

Electrical:

- One (1) 600A Surface Mounted Distribution Panel
- One (1) 400 KW Back-Up Generator
- 3000A Building Power Supply

Project Team:

Owner: City of Pearland Texas
Pearland Independent School District
CM: EMJ Corporation
Architect: PBK
Structural Engineer: Conti, Jumper, Gardner, & Assoc.
MEP Engineer: PBK - MEP Group
Pool Consultant: Aquatic Excellence

Architecture:

Natatorium:
- One (1) 50 Meter X 25 Yard Indoor Competition Pool
- One (1) Four (4) Lane X 25 Yard Therapy Pool with Handicap Access Ramp
- Meeting/Training Room

Recreation Center:
- Competition Gym with Four (4) Lane Track
- Weight Room
- Men's/Women's Locker Rooms
- Offices
- Multi-Purpose Rooms

Structural:

Natatorium:
- Concrete Piers
- Glulam Structural Framing
- Concrete Slab on Grade

Recreation Center:
- Concrete Piers
- Structural Steel Framing
- Concrete Slab on Grade and on Elevated Steel Decking

Matt Smiddy
Construction Option

http://www.engr.psu.edu/ae/theses/portfolios/2010/mds5055/

Table of Contents:

Section	Page #:
Abstract	i
Table of Figures and Tables	iv
Acknowledgements	v
Section 1 - Executive Summary	1
Section 2 - Introduction	2
Section 3 - Project Overview • 3-1 Client Information • 3-2 Project Delivery System • 3-3 Organizational Chart • 3-4 Project Team Contacts • 3-5 CM Staffing Plan	3
Section 4 - Design and Construction Overview • 4-1 Architecture and Enclosure • 4-2 Building Systems • 4-3 Local Conditions • 4-4 Site Layout Planning	7
Section 5 - Project Logistics • 5-1 Milestone Schedule • 5-2 Detailed Project Schedule • 5-3 Construction Cost Estimate	20
Section 6 - Analysis #1 – Concrete Columns with Steel Trusses Vs. Glulam Structural System (Structural – Breadth Topic #1) • 6-1 Background • 6-2 Goals • 6-3 Analysis Method • 6-4 Resources • 6-5 Durability of Concrete, Steel, and Glulam • 6-6 Structural System Re-Design • 6-7 Cost Analysis • 6-8 Schedule Analysis • 6-9 Constructability Analysis • 6-10 Conclusions and Remarks	30
Section 7 - Analysis #2 – AC Chillers Vs. WC Chiller With Cooling Tower (Mechanical – Breadth Topic #2) • 7-1 Background • 7-2 Goals • 7-3 Analysis Method • 7-4 Resources • 7-5 System Selection: • 7-6 Cost Analysis • 7-7 Schedule/Constructability Analysis • 7-8 Energy Analysis • 7-9 Conclusions and Remarks	33
Section 8 - Analysis #3 – Adversarial Project Team Relationships on Design-Bid-Build Projects and other Delivery Methods for Public Projects	37

• 8-1 Background • 8-2 Goals • 8-3 Analysis Method • 8-4 Resources • 8-5 Project Team Analysis • 8-6 Analysis of Other Delivery Methods on Public Projects • 8-7 Applications of MAE Concepts • 8-8 Conclusions and Remarks	
Section 9 - Analysis #4 – Bolted Vs. Welded Glulam Arch Connection • 9-1 Background • 9-2 Goals • 9-3 Analysis Method • 9-4 Resources • 9-5 Feasibility and Constructability Analysis • 9-6 Design Analysis • 9-7 Cost Analysis • 9-8 Schedule Analysis • 9-9 Conclusions and Remarks	40
Section 10 - Summary and Conclusions	43
Section 11 - Works Cited	44
Appendix 3 – Project Overview References	46
Appendix 5 – Project Logistics References	51
Appendix 6 – Analysis #1 (Natatorium Structure) References	67
Appendix 7 – Analysis #2 (Mechanical System) References	79
Appendix 8 – Analysis #3 (Delivery Methods) References	86

Table of Figures and Tables:

Table 3-1.1 Project Funding Distribution
Table 3-2.1 - Design Contract Payment Distribution
Figure 3-2.2 - Project Team Organizational Chart
Figure 3-4.1 - CM Organizational Chart
Figure 4-1.1 - First Floor Plan
Figure 4-1.2 – Second Floor Plan
Figure 4-1.3 - South Exterior Elevation
Figure 4-1.4 - North Exterior Elevation
Figure 4-1.5 - East Exterior Elevation
Figure 4-1.6 - West Exterior Elevation
Figure 4-2.1 - Rec Center 1st Floor Mechanical Room
Figure 4-2.2 - Rec Center 2nd Floor Mechanical Room Locations
Figure 4-2.3 - Natatorium 1st Floor Mechanical Room Location
Figure 4-2.4 - Natatorium 2nd Floor Mechanical Room Location
Table 4-2.5 – Mechanical Room Equipment
Figure 4-2.6 - Construction photo of roof trusses at recreation center
Figure 4-4.1 – Excavation Phase Site Plan
Figure 4-4.2 – Foundations Phase Site Plan
Figure 4-4.3 – Structural Framing Erection Phase Site Plan
Figure 4-4.4 – Enclosure Phase Site Plan
Table 5-2.1 – Milestone Date Comparison
Figure 5-2.2 - Structural and Enclosure Trade Construction Sequence
Figure 5-2.3 - Interior Trades Construction Sequence
Figure 5-2.4 – Recreation Center Construction Phase Locations
Figure 5-2.5 – Swimming Pool Construction Sequence
Table 5-3.1 – Cost Estimate Comparison
Table 5-3.2 – Detailed Structural System Estimate Summary
Figure 5-3.3 – Location of Typical Bay Used for Estimate
Figure 6-1.1 - Natatorium with steel structural system
Figure 6-1.2 - Gymnasium with glulam structural system.
Table 6-1.3 - 2003 IBC Structural Loads
Figure 7-1.1 - Cooling Tower
Figure 7-1.2 - Chillers
Table 7-1.3 – Mechanical System Cost Estimate
Table 7-1.4 - Energy Cost Savings
Figure 9-1.1 - Glulam Arches
Table 9-1.1 - Connection Performance Specification
Table 9-1.2 – Items Added and Removed per Connection

Acknowledgements:

A special thanks to the following people for their contribution to this research project:

Jamie Knise – Facchina Construction of Florida LLC

Scott Stoltz – EMJ Corporation

Matt Luna – EMJ Corporation

Phillip Crissman – EMJ Corporation

Kevin Huff – EMJ Corporation

Van Franks – PBK

Andrea Brinkley – City of Pearland

Skipper – City of Pearland

Mike Parks – RM Rogers

Ashley Rohrscheib – Apel Steel Corporation

John Bechtel – Penn State OPP

Chris Musser – Penn State OPP

Carlo Colella – UMD Department of Capital Projects

Martin Powers – Johnson Controls

Tim Robinson – Carrier

Joe Mulligan – Boland-Trane

Nathan Patrick – Southland Industries

Jim Faust – Penn State AE Department

Chris Magent – Penn State AE Department

Moses Ling – Penn State AE Department

Kevin Parfitt – Penn State AE Department

Robert Holland – Penn State AE Department

Pete Medford – Fort Bend Mechanical

Section 1 - Executive Summary

This report focuses on four construction related analyses of the Pearland Recreation Center and Natatorium building in Pearland, Texas, a Houston, Texas suburb. Two of these four construction related research topics also include a structural analysis and a mechanical analysis. In addition to these analyses this report also contains an overview of the project, including a summary of the project team, the building systems, construction cost, construction schedule, and construction logistics.

Analysis #1 considers replacing the glulam structural system in the natatorium with a concrete column and steel joist structural system. This analysis included a feasibility study as well as a structural analysis to design the structural members. Results from this analysis reflect a construction cost savings of over $600,000 by using the proposed concrete and steel system. Additionally, there are no changes in the construction schedule.

The next analysis looks at replacing the as designed air-cooled chiller mechanical system with a water-cooled chiller and cooling tower mechanical system. This study also includes a mechanical analysis. This study reveals a $48,500 construction cost savings and a $248,000 yearly energy cost savings by using the proposed water-cooled chiller and cooling tower system. Again, this modification has no construction schedule implications.

Next the project team's interaction is analyzed, primarily focusing on the effects of the delivery method. Design-bid-build, the delivery method being used on the project, appears to have resulted in a successful project with no adversarial relationships developing. This project is compared with another project being constructed by the same owner but using the design-build delivery method. It is determined that design-bid-build is the preferred delivery method for public projects, particularly when they are complex such as the Pearland Recreation Center and Natatorium project.

Finally an investigation of the glulam column connection with the concrete footers in the natatorium is conducted. Constructability of the as-designed bolted connection is quite difficult during column erection, as precisely aligning the columns with the bolts is challenging. This analysis considers modifying the connection to a welded connection. Using a welded connection results in no additional construction costs and has no effect on the construction schedule. However, a welded connection would have been much easier to construct.

Section 2 - Introduction

The Pearland Recreation Center and Natatorium project is located at 4141 Bailey Road in Pearland, Texas; a suburb 15 miles south of Houston, Texas. It is being developed through a joint venture between the City of Pearland and the Pearland Independent School District to serve the Pearland community.

The $17 million, 41,817 square foot project began design in March 2007 and construction is scheduled for completion in May 2010. The project, designed by PBK and constructed by EMJ Corporation, is using a design-bid-build delivery method.

The 63,300 square foot recreation center houses a competition gym, indoor running track, racquetball courts, weight room, aerobics room, dance room, locker rooms, administrative offices, and other multi-purpose rooms.

The 41,000 square foot natatorium features a state of the art 25-yard X 50-meter competition pool with two (2) 1-meter and two (2) 3-meter diving boards. There is also a 4-lane 25-yard therapeutic pool with a handicap access ramp.

Section 3 - Project Overview:

3 - 1 Client Information

Pearland Recreation Center and Natatorium is being built to promote recreation and economic activity in Pearland, Texas. The project is being funded by the City of Pearland, Pearland Independent School District, and the Pearland Economic Development Organization as shown below in **Table 3-1.1 - Project Funding Distribution**:

Table 3-1.1 - Project Funding Distribution

Party	Amount Contributed	Source of Funding
City of Pearland, Texas	$13 Million	Tax Revenue
Pearland Independent School District	$3.5 Million and 7-acre building site	School Bond
Pearland Economic Development Organization	$1.5 Million	Tax Revenue

The City of Pearland identified a recreation center and natatorium as 'high' priority in their 2005 master plan. At the same time, Pearland Independent School District recognized a need for a natatorium for their school. The two parties decided to come together to build a joint project. The Pearland Economic Development Organization also recognized the potential economic impacts this project could have on local businesses through additional visitors to the Pearland area. A similar facility nearby, University of Houston's Recreation Center, currently has to turn away requests for facility use due to overbooking, so this new facility could have a significant economical impact on the community.

The master plan called for a project that would serve the community for many years. To meet this goal, the project was flexibly designed to meet any potential changes in regulations. For example the competition pool was designed to be 55 meters long with (2) 2.5 meter wide bulkheads so should regulation pool length change, the facility could easily be modified to meet this new requirement.

The only project deadline is to have the natatorium completed before the start of school in Fall 2010. At this time the project should be completed in June 2010, so this will not be an issue. Currently the project does not have a phased completion and there are no intentions to implement one at this time.

3 - 2 Project Delivery System

A design-bid-build delivery system is being used on the Pearland Recreation Center and Natatorium project. The City of Pearland, Pearland Independent School District, and Pearland Economic Development Organization are building the project as a joint-venture. However, all contracts for the project are held by the City of Pearland. The City of Pearland has hired PBK as the architect and EMJ Corporation as the construction manager for the project.

PBK has selected sub consultants to assist in designing the project. The primary consultants are shown in **Figure 3-2.2 - Project Team Organizational Chart**. The only designer contract held with the City of Pearland is a lump sum Professional Design contract, with payments distributed as shown in the **Table 3-2.1 - Design Contract Payment Distribution**.

Table 3-2.1 - Design Contract Payment Distribution

Deliverable	% of Lump Sum
Schematic Design	15%
Complete Design	15%
Construction Documents	20%
Contractor Procurement	25%
Construction Service	25%

EMJ was selected as general contractor through a 'Best Value' selection method. The City of Pearland considered items such as cost, schedule history, references, and proposed specialty contractors during this selection process. EMJ contracted specialty contractors to perform all the work on site. They hold lump sum contracts with all their subs as shown in **Figure 3-2.2 - Project Team Organizational Chart**. A complete list of specialty contractors on the project is available in **Appendix 3**.

The project design was essentially completed prior to contractor selection, so the design-bid-build delivery method with a lump sum contract is appropriate for this project.




Figure 3-2.2 - Project Team Organizational Chart

The City of Pearland required the following insurance to be held by the contractors and design professionals on the project:

-Worker's Compensation as per Texas State Requirements

-Commercial General Liability Insurance:

-$1,000,000 for each occurrence

-$2,000,000 general aggregate limit

-$2,000,000 product-completed operations aggregate limit

-$1,000,000 personal and advertising injury limit

-Auto liability insurance coverage of $1,000,000

-Employer's liability insurance coverage of $1,000,000 per accident or disease

-Umbrella liability insurance coverage of $5,000,000

-Professional liability insurance coverage of $1,000,000.

-Builder's risk insurance in equivalence to total repair and replacement charges of every incident.

3 - 3 Project Team Contacts

City of Pearland – Andrea Brinkley – Project Manager

EMJ Corporation – Scott Stoltz – Project Manager

EMJ Corporation – Kevin Huff – Project Engineer

EMJ Corporation – Phillip Crissman – Project Superintendent

PBK – Van Franks – Principle

3 - 4 CM Staffing Plan

The CM (EMJ Corp) project team for the Pearland Recreation Center and Natatorium project consists of a Vice-President in Charge, a Project Manager, a Project Engineer, a Superintendent, and an Assistant Superintendent.

The Vice-President in Charge, Project Manager, and Project Engineer work from the EMJ home office in Dallas, TX and visit the project site about twice a month. The Superintendent and Assistant Superintendent are on-site in Pearland, TX at all times.

The Project Engineer, Superintendent, and Assistant Superintendent work full time on the project while the Project Manager and Vice-President in Charge are both part time on the project and oversee other projects as well. **Figure 3-4.1 - CM Organizational Chart** shows the organization of the staff on this project.





Figure 3-4.1 - CM Organizational Chart

Section 4 - Design and Construction Overview


4 - 1 Building Architecture/Enclosure

The Pearland Recreation Center and Natatorium houses a recreation center and natatorium as shown in **Figures 4-1.1 – First Floor Plan** and **4-1.2 – Second Floor Plan**. The building spans 638'-1" and is 230'-1" wide. The natatorium is located on the eastern half of the building and is connected to the recreation center on the opposite half of the building.



Recreation Center **Natatorium**

Figure 4-1.1 - First floor plan



Recreation Center **Natatorium**

Figure 4-1.2: Second floor plan

The 2-story recreation portion of the building contains a double height competitive gym seating 588 spectators and a raised 4-lane running track around the perimeter. There is also a dance room, aerobics room, weight room, 2 racquetball courts, locker rooms, offices, and other multi-purpose rooms.

The double height natatorium contains an 8-lane 50 meter competition pool and a 4-lane 25 yard instructional pool with a handicap ramp. The competition pool includes a moveable bulkhead, (2) 1-meter diving boards, and (2) 3-meter diving boards. There is seating for 694 spectators in bleachers surrounding the competition pool. There are also equipment rooms and training rooms in this portion of the building.

Building Codes

2003 International Building Code

2003 International Plumbing Code

2003 International Mechanical Code

2003 International Electrical Code

2003 International Energy Code

2003 International Fire Code

2003 International Gas Code

1994 Texas Accessibility Standards

1992 Americans with Disabilities Act

Zoning

Zoning District – 'GB' (General Business)

	Requirements	Actual
Minimum Lot Size	22,500 Square Feet	330,090 Square Feet
Minimum Lot Width	150'-0"	727'-7" (Frontage on Bailey Road)
Minimum Lot Depth	125'-0"	453'-8"
Building Setback: Front	25'-0" Minimum	212'-6"
Building Setback: Rear	25'-0" Minimum	32'-9"
Building Setback: Side	10'-0" Minimum	34'-6"
Height Restriction	45'-0" Maximum Height	44'-11"

Historical Requirements

There are no historical requirements on this project.

Building Facades

The facades are primarily face brick on horizontally reinforced 8” CMU with rigid insulation and damp proofing between. The facades by the recreation center and natatorium entrances are calcium silicate masonry units on horizontally reinforced 8” CMU with rigid insulation and damp proofing between. All the glazing is ¼” Tinted Tempered Float Glass.

The south façade, facing Bailey Road is 25% glazing as shown in **Figure 4-1.3 - South Exterior Elevation**.




Figure 4-1.3 - South Exterior Elevation

The north façade has 10 windows as shown in **Figure 4-1.4 - North Exterior Elevation.**




Figure 4-1.4 - North Exterior Elevation

The east façade has a series of strip windows along the recreation center entrance as shown in **Figure 4-1.5 - East Exterior Elevation**.




Figure 4-1.5 - East Exterior Elevation

The west façade has 10 windows plus a strip window at the recreation entrance as shown in **Figure 4-1.6 - West Exterior Elevation.**

.




Figure 4-1.6 - West Exterior Elevation

4 - 2 Building Systems

Demolition

No demolition was required.

Excavation

The site is at an elevation of 14’ above sea level. It was necessary to excavate to about 14’ for the foundations. For this reason it was necessary to dewater the site. This was done using well points throughout the site. Excavation was done with a 1:1 layback so no temporary support was needed.

Structural Framing System

The Recreation center has a structural steel frame. The columns are all tube steel while the beams are W-sections with K-series joists supporting 18ga galvanized 1-1/2” deep non-composite floor decking and 22ga galvanized 1-1/2” deep Type “B” steel non-composite roof decking. All connections between W-sections are bolted and the connections to the tube steel are welded connections. The steel was erected using a 50-Ton and 80-Ton Truck Crane.

The Natatorium has glulam columns supporting glulam purlins which support a 3” wood deck. The glulam system was erected using a 100-Ton and 75-Ton Truck Crane.

Cast-In Place Concrete

The only cast-in-place concrete in this project was the slabs and foundations. The foundation consisted of spread footings on drilled piers. The footings used stick-built forms and were poured with a pump truck. There is a 5” thick reinforced concrete slab-on-grade with a vapor barrier that extends throughout the entire building foundation. There is also a 3” thick concrete slab on WWF on the elevated slabs. The slab-on-grade was placed using a pump truck in 4 different pours. The elevated slabs at the second level and the roof were each poured in 3 pours.

Precast Concrete

There is no precast concrete on this project.

Mechanical System

The recreation center is serviced by five (5) mechanical rooms located as shown below in **Figures 4-2.1 - Rec Center 1st Floor Mechanical Room Locations** and **4-2.2 - Rec Center 2nd Floor Mechanical Room Locations**:




Figure 4-2.1 - Rec Center 1st Floor Mechanical Room Locations




Figure 4-2.2 - Rec Center 2nd Floor Mechanical Room Locations

The Natatorium is serviced by two (2) mechanical rooms as shown below in **Figures 4-2.3 - Natatorium 1st Floor Mechanical Room Location** and **4-2.4 - Natatorium 2nd Floor Mechanical Room Location**:




Figure 4-2.3 - Natatorium 1st Floor Mechanical Room Location




Figure 4-2.4 - Natatorium 2nd Floor Mechanical Room Location

The mechanical rooms contain mechanical equipment as shown in **Table 4-2.5 – Mechanical Room Equipment**.

Table 4-2.5 – Mechanical Room Equipment

Location	Item
RM1a	Two (2) Air Cooled Chillers
RM1b	Four (4) End Suction Pumps
RM2a	Two (2) Air Handling Units, Two (2) Boilers, and One (1) End Suction Pump
RM2b	Three (3) Air Handling Units
RM2c	Four (4) Air Handling Units
NM1	One (1) Air Handling Unit and One (1) Condenser
NM2	Two (2) Air Handling Units

Air is distributed throughout the building using rectangular and flex duct. These ducts then connect to Constant Air Volume Terminals in each room.

Fire Suppression System

The building has a Wet Pipe Pre-Action Fire Sprinkler System that is to be installed to a performance spec of:

Public Spaces, Classrooms, and Offices: 0.10 GPM/SF over the most remote 1,500 SF.

Mechanical Rooms, Storage Areas, and Service Areas: 0.15 GPM/SF over 1,500 SF.

Electrical System

The electrical system for the Pearland Recreation Center and Natatorium has a 3000A building supply with a 600A Surface Mounted Distribution Panel. There is also a 400 KW emergency back-up generator for the building.

Masonry

The entire building has an 8" horizontally reinforced non-load bearing CMU enclosure. There is reinforcing at 16" on-center. There is also a bond beam every 8' (12-courses of block).

Attached to the CMU is a face brick veneer connected by masonry ties every 4-courses of CMU. Between the CMU and face brick there is 1 ½ inch rigid insulation and an air space. Additionally, the CMU has a damp proofing applied to it.

Roofing

The roof in the recreation center is a steel truss system (shown in **Figure 4-2.6 - Construction photo of roof trusses at recreation center**) while the roof in the natatorium is a glulam truss system. The roofing system throughout the recreation center and natatorium consists of a standing seam metal roof on a fully adhered waterproof membrane. The roofing system over the main entrance to the building on the south side, a small strip between the recreation area and natatorium, and a small portion of the north side of the natatorium is modified bitumen.



Figure 4-2.6 - Construction photo of roof trusses at recreation center

Curtain Wall

There are no curtain walls in this building.

Sustainable Features

This building has no sustainable features.

4 - 3 Local Conditions

Labor

The project site is located in a suburb of Houston, TX; the 4th largest city in the US. This location enables easy access to a diversely skilled labor force. For this reason labor availability will not be a problem.

Weather

Houston, TX has a warm and mild climate. While winter weather will not be an issue, there is the potential for tropical weather to affect the project during the fall months. Additionally, since the project is located in a region that is prone to tropical weather, there will be more stringent building codes and inspections.

Geography

The project is located on a 7-acre plot of land in an unpopulated portion of the suburb of Houston, Texas. There is ample area for construction lay down and parking.

The project site is at a very low elevation (+14'). Because of the low site elevation, ground water will be a serious consideration during excavation. It will be necessary to de-water the site during all excavation activities.

Sustainability

Sustainable construction practices are not predominant in the Houston area. It is uncommon for construction projects to apply sustainable practices such as construction material recycling, etc.

Tipping Fees:

It is common practice in the Houston area to not recycle construction material. For this reason, all construction waste is placed in the same dumpster on site. Removal of this waste costs $316 per 40 cubic yard dump. This is $7.9 per cubic yard of waste.

4 - 4 Site Layout Planning

Site layout for the Pearland Recreation Center and Natatorium is greatly simplified due to a large site. Consistent across all phases of the project are the dumpsters in the northeast corner of the site with a dedicated entrance off of Bailey road for access to empty them, porta-potties in the northeast corner of the parking lot, the construction offices on the east side of the site, the temporary transformer in the southeast corner of the building, temporary utilities running to the southeast corner of the building from Bailey Rd, contractor parking on the south side of the site, and the site entrance off of Bailey road on the south side of the site.

Site layout for the excavation phase of construction is shown in **Figure 4-4.1 – Excavation Phase Site Plan**. Excavation will begin from the northwest corner of the building and proceed towards the southeast corner of the building as shown. Dump trucks will arrive and circulate through the site to remove soil as shown.




Figure 4-4.1 – Excavation Phase Site Plan

Figure 4-4.2 – Foundations Phase Site Plan shows the site layout for the foundations phase of construction. Foundations work will again progress from the northwest corner to the southeast corner of the building. A rebar yard, with access provided for flatbed rebar truck deliveries, is provided in the southwest corner of the site. The pump truck and concrete trucks will circulate as shown. They will only be present on site during concrete pours. The location of the pump truck will move eastward on the site as work progresses. A contractor material storage area is also provided in the southeast corner of the site.




Figure 4-4.2 – Foundations Phase Site Plan

The project site begins to become more congested as the structural framing erection phase of construction begins. Site layout for this phase is shown in **Figure 4-4.3 – Structural Framing Erection Phase Site Plan**. Erection of the steel and glulam will proceed from the west end of the building to the east end. Steel and glulam members will be delivered and unloaded in the shake-out area in the southwest corner of the site. Two cranes will be erecting the steel and glulam on site, one on the north side and one on the south side of the building as shown. Steel joists will be delivered to this shake-out area as well, but will then be moved to the joist shake-out area on the north side of the site to be prepared for final erection. There will be an access point for stocking material to the building located at the southwest corner of the building. This will be done using front loaders.




Figure 4-4.3 – Structural Framing Erection Phase Site Plan

Enclosures is the final phase of construction. Work in this phase will progress in a clockwise direction, first around the recreation center than proceeding to go around the natatorium. There will be a contractor material staging area in the southwest corner of the site. This area will be used by contractors to unload materials from trucks as shown. There are also material storage areas on the north side and in the southeast corner of the site. Materials will again be stocked to the building through the access point at the southwest corner of the building using front loaders. **Figure 4-4.4 – Enclosure Phase Site Plan** shows the site layout for this phase of construction.




Figure 4-4.4 – Enclosure Phase Site Plan

Section 5 - Project Logistics

The project schedule for the Pearland Recreation Center and Natatorium begins with commencement of design on March 1, 2007 and ends with substantial completion on May 12, 2010.

5 – 1 Milestone Schedule

After site work is completed, the recreation center will be constructed separately from the natatorium. While they are one building, the structural systems and building features of the two portions are completely different so separate construction of the two building sections seems most efficient. Through each phase of construction, the recreation center will generally precede construction of the natatorium.

Site Work

The site work activity contains all work done for site preparation as well as for the parking lot, which will be constructed at the beginning of the project to allow for a cleaner construction site.

Foundations

The foundations in the natatorium will commence once the excavation has been completed for the swimming pools. This excavation will be performed while the foundations are being constructed on the recreation center.

Structural

The structural system in the recreation center is very simple and does not have anything important to note. The natatorium has 14 large glulam beams that will span the swimming pools. The structural system in the natatorium will begin after the recreation center's structural system has been completed and will be constructed by a separate contractor due to the glulam material.

Finishes

The finishes in the recreation center again don't have anything unique to note, however the natatorium must have the interior finishes completed prior to beginning the swimming pool finishes (tiles, etc.) in order to avoid damage to the expensive work that will be put in place in the swimming pool.

The project schedule for this project is relatively simple. The key item to notice when viewing the schedule is the separation in construction of the two (recreation center and natatorium) portions of the building. See **Appendix 5** for the complete project summary schedule.

5 – 2 Detailed Project Schedule

Construction of the Pearland Recreation Center and Natatorium will begin with the Notice to Proceed on April 20, 2009 and conclude with Substantial Completion on May 12, 2010. The complete detailed schedule is available in **Appendix 5**. To create the construction schedule for the project the building was split into two portions: recreation center and natatorium. This was done because these two portions of the building are very different and will be constructed in a different manner due to the swimming pool and glulam structural system in the natatorium. **Table 5-2.1 – Milestone Date Comparison** compares some key construction milestone dates in the recreation center versus the natatorium.

Table 5-2.1 – Milestone Date Comparison

Milestone	Recreation Center	Natatorium
Notice to Proceed	4/20/2009	4/20/2009
Top Out	8/7/2009	8/30/2009
Dry-In	10/23/2009	12/9/2009
Substantial Completion	5/12/2010	4/28/2010

Structure and Enclosure

Construction of the building's structural system and enclosure is sequenced as shown in **Figure 5-2.2 - Structural and Enclosure Trade Construction Sequence**




Figure 5-2.2 – Structural and Enclosure Trade Construction Sequence

Interiors

Following 'Dry-In,' a 'parade of trades' construction sequence is applied; that is only one trade works in each space at a time and each trade follows the previous. **Figure 5-2.3 - Interior Trades Construction Sequence** shows the order of the interior 'parade of trades'.




Figure 5-2.3 - Interior Trades Construction Sequence

Following the interior 'parade of trades' a number of specialty items are installed, such as casework, gym flooring, and gym equipment. See the detailed schedule in **Appendix 5** for all activities.

Recreation Center

Construction of the recreation center progresses counterclockwise through the building in three phases. **Figure 5-2.4 – Recreation Center Construction Phase Locations** shows the locations of these three phases.




Figure 5-2.4 – Recreation Center Construction Phase Locations

Second floor activities only have two phases since the gym is double height and the small portion of phase three that has a second level is combined with phase 2 for the second floor.

Natatorium

There is no phasing of construction in the natatorium as there was in the recreation center. Construction sequencing in the natatorium will revolve around the swimming pool construction. See **Figure 5-2.5 – Swimming Pool Construction Sequence** for the sequence of swimming pool construction activities.




Figure 5-2.5 – Swimming Pool Construction Sequence

Construction of other portions of the natatorium will be occurring throughout the pool construction; however it is critical that the finishing and tiles in the swimming pool are the last activity to occur in the swimming pool area in order to protect the work. Immediately after this is completed, the pool will be filled with water and testing and chemical balancing will begin.

5 – 3 Construction Cost Estimate

Actual Cost

Total Actual Building Construction Cost: $15,137,233

Actual Building Construction Cost/SF: $144.00/SF

Total Project Cost: $16,901,509

Project Cost/SF: $160.79

By System

System	Total Cost ($)	Cost/SF ($)
Structural Steel (Erection Included)	$1,054,385	$5.8
Cast-In Place Concrete	$1,166,021	$11.09
Masonry	$1,223,500	$11.64
HVAC	$1,907,000	$18.14
Electrical	$41,936	$0.40
Plumbing	$499,027	$4.75
Fire Protection	$195,450	$1.86
Elevators	$41,936	$0.40
Roofing	$609,900	$5.81

NOTE: For confidentiality purposes the actual estimate has not been posted.

Estimated Construction Cost

The estimated cost for the project was created using D4Profiler and RS Means SF Cost Data. D4Profiler takes real cost data from similar past projects and modifies it to meet the specified building requirements.

D4Profiler had a very similar project, a recreation center with a large natatorium, just outside of Cincinnati, Ohio. This project was almost the exact same size as well the Pearland project as well. The cost was within 1% of the actual cost. This cost was the total project cost, not just the construction cost. This total project cost estimate is included in **Appendix 5**.

Obtaining an RS Means estimate was more difficult. A separate cost estimate was obtained for the recreation center (using the 'Gymnasium' building type in RS Means) and the natatorium (using the 'Swimming Pool, Enclosed' building type in RS Means). A problem that arose was that the cost data provided in RS Means was for projects much smaller than the Pearland project. To account for this it was necessary to extrapolate the table values. The cost estimates for these two portions were then combined to obtain a total building cost. This price was again within 1% of the actual cost. This estimate is only for construction costs and is included in **Appendix 5** with all the calculations that were performed.

These estimates are shown in the **Table 5-3.1 - Cost Estimate Comparison** below.

Table 5-3.1 – Cost Estimate Comparison

Method	Total Cost ($)	Cost/SF ($)	Price Includes:
D4Cost	$16,786,542	$159.87	Total Project Cost
RS Means SF Data	$15,043,887	$143.28	Construction Cost

Detailed Structural Cost Estimate

In addition to the Parametric Cost Estimate from D4Profiler and the SF Cost Estimate from RS Means, a detailed structural system construction cost estimate was also performed. A detailed structural system construction cost estimate for the Pearland Recreation Center and Natatorium project yielded just over $4,425,000, or about $42/SF. This cost includes all labor, equipment, and material required for construction of the caissons, concrete, structural steel, steel decking, joists, trusses, wood decking, and glulam structural framing. A break-down of the cost estimate is shown in **Table 5-3.2 – Detailed Structural System Estimate Summary**. The complete estimate as well as the calculations are available in **Appendix 5**.

Table 5-3.2 – Detailed Structural System Estimate Summary

Cost Breakdown Summary

Dev.	Item	Total Cost
02465	Caissons	$526,841.25
03220	Rebar	$60,681.51
03221	WWF	$18,041.18
03310	3000 psi concrete	$145,747.62
03311	3500 psi concrete	$36,687.77
03312	Concrete Finishing	$15,161.58
03313	Concrete Forming	$471,115.84
03314	Vapor Barrier	$123,562.53
03315	5" Concrete Edge Form	$2,729.14
03316	3" Pour Stop	$821.42
03500	Roof Deck	$626,272.50
05100	Structural Steel	$702,167.12
05200	Steel Floor Joists	$390,755.16
05300	Metal Deck	$66,784.03
06100	Wood Trusses	$170,000.00
06110	Glulam (Decking, Purlins, and Columns)	$1,070,000.00
	Total Cost	**$4,427,368.67**

Pricing for the estimate was obtained using RS Means 2009 Building Construction Cost Data and contractor information. RM Rodgers provided the glulam pricing and Tectum Inc. provided pricing for the Tectum E roof decking system over the recreation center. All other pricing information came from RS Means.

The estimate was created by doing a detailed take-off of a typical bay of the building and extrapolating. **Figure 5-3.3 – Location of Typical Bay Used for Estimate** shows the 2520 SF (both levels) area, between gridlines G-J and 1-2, which was used.




Figure 5-3.3 – Location of Typical Bay Used for Estimate

Recreation Center

Using the total cost estimate obtained from this bay, a cost/SF value was calculated and multiplied by the square footage of the recreation center. This cost/SF did not include the Tectum 'E' roof decking or roof trusses. The cost of these two items was estimated for the entire recreation center then added to the extrapolated cost estimate. See **Appendix 5** for the complete detailed cost estimate.

Natatorium

Modifications had to be made to the cost/SF value to estimate the natatorium's structural system cost since the structural system is glulam instead of steel, like the recreation center. Additionally, there are no elevated slabs in the natatorium. To account for these differences the structural steel and elevated deck costs were subtracted from the recreation center's cost/SF. This new cost/SF was then multiplied by the total square footage of the natatorium. This extrapolated value was added to the glulam columns, purlins, and decking value provided by

RM Rodgers for the total natatorium structural system construction cost. See **Appendix 5** for the complete detailed cost estimate.

General Conditions Estimate

A detailed general conditions cost estimate was also calculated. A general conditions cost of just over under $2 million was estimated for the Pearland Recreation Center and Natatorium project. This estimate was obtained using pricing from RS Means and EMJ Corporation. See **Appendix 5** for the complete estimate.

The general conditions estimate contains 5 portions: project management, temporary facilities, temporary utilities, cleaning, and miscellaneous. Project management and insurance, bond, and O&P are the primary costs in the general conditions, totaling almost $1.9 million. Temporary facilities include items such as job office trailers, temporary sanitary facilities, and barricades. All material hoisting (lifts, cranes etc.) and heavy equipment are to be provided by the contractors so it was not necessary to include these items. Temporary utilities consist of costs for temporary electric, water, and telephone during construction. The cleaning section will pay for weekly site clean-up and final building clean-up. A miscellaneous section with items such as hand tools, safety, and blue prints is also included. A 2% bond, 3% insurance, and 10% overhead and profit are also included in the estimate. These percentages are of the total project cost ($16,786,542 as per Tech #1 estimate).

Section 6: Analysis #1 – Concrete Columns with Steel Trusses Vs. Glulam Structural System (Structural – Breadth Topic #1)

6 – 1 Problem:

Unlike the steel structural system in the recreation center, the natatorium has been designed using a glulam structural system. It is unusual for a natatorium to use a glulam structural system. Additionally, glulam is significantly more expensive than concrete and steel and presents unique challenges during construction. The designer insists that structural steel, even with special coatings, corrodes and deteriorates in the humid environment of natatoriums.




Figure 6-1.1 - Natatorium with steel structural system. Courtesy of Penn State

6 – 2 Goal:

Determine the structural and economic feasibility of using a steel structural system in place of the currently designed glulam system in the natatorium, including identifying the durability of steel and glulam in a natatorium's humid environment.



Figure 6-1.2 - Gymnasium with glulam structural system. Courtesy of Structure Mag

6 – 3 Analysis Method:

1) Determine the durability of concrete, steel and glulam structural systems in a natatorium environment, including all maintenance issues and costs.
2) Design a structural concrete and steel system to replace the glulam system.
3) Calculate the cost savings associated with using a structural concrete and steel system
4) Analyze the schedule impacts of using a structural concrete and steel system
5) Consider the constructability effects of using structural concrete and steel

6 – 4 Resources:

1) Penn State OPP – Chris Musser
2) University of Virginia Capital Projects
3) University of Maryland Capital Projects
4) University of Houston Capital Projects
5) RS Means 2009 Cost Data
6) R.M. Rodgers – Miles Parks
7) Designers with experience in glulam and concrete and steel structural systems in natatoriums.
8) MS Project
9) Pearland Recreation Center and Natatorium project team.

6 – 5 Durability of Concrete, Steel and Glulam:

Initially the objective of this analysis was to design a completely steel structural system in the natatorium. As research of the steel structural system progressed, it was suggested by structural engineers at a number of university's capital projects groups that a structural system consisting of concrete columns and steel girders/joists be used instead. Paint on steel chips very easily and when exposed to water (like the bases of columns would be) the steel would begin to rust. Alternatively, if concrete was used the only concern would be water penetrating the concrete and rusting the rebar. Since the bases of the columns will not be saturated with water this scenario can be ignored. Similarly, since the steel joists and girders would be located up in the ceiling, the chance of paint being chipped on them would be very low. Additionally, the only water concern would be humidity which should not cause the steel to rust, especially if the paint on the steel is not chipped.

6 – 6 Structural System Re-Design:

After a concrete and steel structural system was decided upon it was necessary to design the system. The system was designed using the 2003 International Building Codes shown in **Table 6-1.3 – 2003 IBC Structural Loads**. The roof slope was set at 3:12.

Table 6-1.3 -2003 IBC Structural Loads

Type of Load	Design Load
Roof	20 lb/SF
Dead Weight	20 lb/SF
Wind	120 mph for 30 sec gust – exposure C – importance factor of 1.15

The resulting design consisted of (468) 25' 14k1 joists at 4' o.c. These joists rest on (14) 140' 104SLH22 girders at 25' o.c. The steel system rests on (28) 10" X 10" square concrete columns with 4-#5's. The design calculations as well as the Steel Joist Institute and Concrete Reinforcing Steel Institute sizing sheets that were used are attached in **Appendix 6.** It is important to note that throughout this system redesign it was assumed that the CMU walls in the natatorium would support the structure laterally.

6 – 7 Cost Analysis:

Once a new structural system was designed it was necessary to determine the cost implications of this design modification. To do this RS Means 2009 Cost Data was used. Using this cost data, a total system cost of $469,738 was obtained. This was a $600,262 savings over the $1,070,000 glulam structural system (supplied by R.M. Rodgers, glulam contractor on project) that it replaced. An additional $30,000 was incorporated into the steel system to cover extra connection costs (plates for column-beam connection, etc.) Cost calculations as well as RS Means cut sheets are included in **Appendix 6**.

6 – 8 Schedule Analysis:

A schedule analysis was performed to analyze the effects of this new system on the construction schedule. It was discovered that there was no effect on the schedule. As shown in the modified schedule (shows only the portion of the schedule that included this modification) in **Appendix 6**, the concrete columns are poured while steel is being erected on the Recreation Center and when steel erection is completed on the Recreation Center, the erectors simply continue work on the building with erection in the Natatorium. Prior to the system modification, the steel erectors would have been done once the Recreation Center was complete and the glulam erectors would begin their structural system erection by erecting the glulam members. The only difference with the modified system is that instead of the glulam erectors working on the Natatorium following completion of the Recreation Center's steel, there would be steel erectors erecting steel in the Natatorium.

6 – 9 Constructability Analysis:

Modification of the structural system makes it more easily constructible. The 100 Ton truck crane that was used to erect steel in the Recreation Center would already be on site and would be able to lift all the steel members in the natatorium so no additional cranes would be needed. Additionally, a constructability challenge with the glulam system was the erection of the arches, particularly aligning the bolted connection to the footer. By using the concrete columns this concern could be neglected. Another benefit of this new system is that it would eliminate the need for a glulam subcontractor and would therefore result in one less subcontractor that needs to be on site and managed.

6 – 10 Conclusions and Remarks:

Modification of the natatorium structural system from glulam to steel and concrete resulted in a cost savings, no schedule change, and a more easily constructible building. The objective of this analysis was successful in identifying a preferable alternative to the as-designed natatorium structural system.

Section 7: Analysis #2 – AC Chillers Vs. WC Chiller With Cooling Tower (Mechanical – Breadth Topic #2)

7 – 1 Problem:

During the design phase of construction the owners of the Pearland Recreation Center and Natatorium insisted on using a cooling tower system to cool the water for the building's mechanical system. PBK, the project architect and MEP engineer, convinced them that using a cooling tower system with a water cooled (WC) chiller would be unreasonable since the building was only 105,000 SF. Instead they suggested using an air cooled (AC) chiller system, which would be a more economical choice given the size of the building.



Figure 7-1.1 - Cooling Tower (Courtesy of Zetacorp)




Figure 7-1.2 - Chillers (Courtesy of Tatro Plumbing)

7 – 2 Goal:

The goal of this research topic is to compare the cost of a cooling tower and WC chiller and AC chiller system in order to determine the more economical option. Cost data is already available for the AC chiller system; however it will be necessary to size and develop a construction cost estimate for a WC chiller and cooling tower system.

7 – 3 Analysis Method:

1) Determine the cooling loads on the Pearland Recreation Center and Natatorium
2) Select a cooling tower and WC chiller system that would satisfy the required cooling loads for the building.
3) Obtain construction cost information for the selected WC chiller and cooling tower system.
4) Compare the cost of the WC chiller and cooling tower system to the as designed AC chiller system to determine the more economical option.
5) Consider constructability factors that may make either option more feasible.
6) Consider life-cycle cost and maintenance factors for each option.

7 – 4 Resources:

1) Professor James Freihaut and AE – 310 HVAC Fundamentals course materials
2) Pearland Recreation Center and Natatorium project MEP engineer – PBK MEP
3) Fort Bend Mechanical
4) EMJ Corporation
5) Southland Industries – Nathan Patrick
6) Chesapeake Systems – David Jaworski
7) Boland-Trane – Joe Mulligan

7 – 5 System Selection:

The first step in analyzing the modification of the mechanical system was to design and select a suitable system. As previously mentioned, the current AC chiller would need to be replaced with a WC chiller as well as a Cooling Tower. The 2 as-designed AC chillers each had a capacity of 138 Tons, an entering water temperature of 56d F, a leaving water temperature of 42dF, and a flow rate of 240 GPM. Using these previous design specs and the fact that the project was located in Houston, TX it was determined that the new WC Chiller/Cooling Tower system be designed with a DB temperature of 92dF, a WB temperature of 77dF, a capacity of 276 tons and a 85dF condenser water temperature. Using these parameters it was discovered that the 2 AC chillers could be replaced with only 1 WC chiller. Similarly, the Cooling Tower was sized using an 85dF entering water temperature, a 95dF leaving water temperature and a 828 GPM (3 GPM/ton) flow rate. Product cut sheets for the WC chiller and Cooling Tower supplied by Boland-Trane and Chesapeake Systems are available in **Appendix 7**.

7 – 6 Cost Analysis:

Once the new mechanical system was designed it was then necessary to estimate the cost of the new system and compare it to the previous system. To do this, quotes were obtained from Chesapeake Systems and Trane-Boland for the cooling tower and WC chiller respectively. Labor costs for the installation of this equipment and additional pumps and piping required for the cooling tower were obtained from RS Means 2008 Cost Data. Cost information for the as-designed system was obtained from Fort Bend Mechanical, the mechanical contractor on the project. The new mechanical system offered a $48,523 savings over the previous system. **Table 7-1.3 – Mechanical System Cost Estimate** contains a summary of this comparison and the complete cost estimate calculations are contained in **Appendix 7**.

Table 7-1.3 – Mechanical System Cost Estimate

Item	Cost	Source
Cooling Tower		
Material	$30,171	Chesapeake Systems
Labor	$2,650	RS Means 2008 Cost Data, Pg. 374
Additional Pumps & Piping		
Labor & Material	$26,082	RS Means 2008 Cost Data, Pg. 374
Water Cooled Chiller		
Material	$93,840	Boland-Trane
Labor	$11,700	RS Means 2008 Cost Data, Pg. 373
Additional Structural Support for Cooling Towers		
Labor & Material	$15,557	Fort Bend Mechanical
Total Cost for New System	$180,000	
Total Cost for Old System	$228,523	
Initial Cost Savings with New System	$48,523	

7 – 7 Schedule/Constructability Analysis:

There are three potential constructability issues that would need to be considered with the new WC Chiller/Cooling Tower system that were not present with the old system:

1) The Cooling Tower would require additional structural support in the concrete slab that it would be placed on. This issue should not pose a problem, given the concrete slab is properly reinforced when it is constructed.

2) The Cooling Tower would require a crane for placement. It would be important to properly plan for this and ensure that adequate access is left to the mechanical courtyard on the north side of the building where it would be placed.

3) Previously, the AC chiller had been placed outside in the mechanical courtyard. With the new system, the cooling tower would be placed here and the water cooled chiller would need to be placed inside. There would be room for this equipment in the mechanical room on the northwest corner of the building. However it is important to consider access to this room for chiller installation.

While none of these issues should be a problem, it would be important to give them careful consideration while planning construction to ensure that adequate measures would be taken to account for them. This system modification should have no effect on the schedule since the only additional activities will be cooling tower placement and some extra pumps and piping which could be included in the current mechanical system construction duration.

7 – 8 Energy Cost Analysis:

An energy cost comparison between the two systems was also performed. The old air-cooled chiller system consumed 1.3 KW/Ton for each chiller, or a total of 718 KW. Using a water-cooled chiller and cooling tower the total energy usage would be only 427 KW. Energy information for the water-cooled chiller came from Boland-Trane and for the cooling tower a COP of 4 was assumed and the KW/ton value was calculated from that. Assuming energy costs of 10 cents per KWh in Houston, TX the total energy cost savings using the new system are shown in **Table 7-1.4 - Energy Cost Savings**. All the calculations for this cost comparison can be found in **Appendix 7**.

Table 7-1.4 - Energy Cost Savings

Time Period	Cost Savings
Daily	$698
Monthly	$20,707
Yearly	$248,488

7 – 9 Conclusions and Remarks:

Modification of the mechanical system from an air cooled chiller system to a water cooled chiller with a cooling tower system presents a savings of almost $50,000 in construction costs, almost $250,000 a year in energy costs, and no change in construction schedule duration.

While the new system is preferred economically, there are some additional factors that would need to be taken into consideration during construction such as additional structural reinforcing and construction logistics in mechanical equipment placement. Similarly, a cooling tower will require additional consideration throughout its life-time to ensure that the water in the cooling tower is controlled. Considering the building contains two swimming pools, this water maintenance should not be an issue for the owner as they should already have water control systems in place for the swimming pools and the monitoring of the cooling tower water could just be folded into these duties. In conclusion, a water cooled chiller and cooling tower system could be beneficial for the Pearland Recreation Center and Natatorium project.

Section 8: Analysis #3 – Adversarial Project Team Relationships on Design-Bid-Build Projects and other Delivery Methods for Public Projects (MAE Focus Topic)

8 – 1 Problem:

Projects utilizing the traditional Design-Bid-Build delivery method tend to result in adversarial relationships between project team members. As Pearland Recreation Center and Natatorium approaches completion, it seems that the project is unique in that the project team is still working together effectively and the project is setup for an on-schedule, on-budget completion. It appears that this is a great opportunity to analyze some attributes of a successful project team using this delivery method. Design and construction of the project has been seamless. Throughout the design phase there was beneficial owner-designer interaction that resulted in many features of the building being modified to more effectively meet the owner's needs. During construction there were few problems encountered and the project is currently scheduled to be completed well ahead of schedule.

8 – 2 Goal:

The goal of this research is to determine the factors that contributed to the project's apparent success, including factors such as project team selection and contracting method. Conclusions obtained from this research will be targeted at helping owners select successful teams for their upcoming projects. Additionally, this research will potentially identify an ideal delivery method for public projects.

8 – 3 Analysis Method:

1) Issue questionnaires to project team members to collect their opinions of why the project was successful, as well as to determine if there were any aspects of the project that could have been improved.
2) Compare questionnaire responses to identify commonalities.
3) Interview select project team members to identify specific attributes that have contributed to the project's success.
4) Study the contract documents in order to locate language that contributed to the project's success.
5) Identify aspects of the project team selection process that led to the successful outcome.
6) Interview other public project teams using various delivery methods to potentially identify an ideal project delivery method for public projects.

8 – 4 Resources:

1) Project team surveys
2) Project team interviews
3) Project contract documents
4) Project team selection method
5) Case studies – Other Public Projects
6) AE – 572 Project Development and Delivery Planning course materials

8 – 5 Project Team Analysis:

Analyzing the Pearland Recreation Center and Natatorium's project team began by sending out a survey to the general contractor, EMJ Corporation; owner, City of Pearland; and architect, PBK. Responses were obtained from the general contractor and owner, however after numerous attempts an answer was never received from the architect. These surveys are attached in **Appendix 8**. Upon receipt of the survey responses it became apparent that the project team was working very well together and that all members had a cordial relationship. Additionally, the traditional design-bid-build delivery method was working very well. The City of Pearland was very satisfied with EMJ's work. They were impressed with the management of the company and their effort to achieve a successful project.

After digesting the results from the surveys, phone interviews were executed with the general contractor and architect. These phone interviews developed the concept of 'the ideal delivery method for public projects' - the final result of this research topic. During the phone interviews both the general contractor and owner were strong advocates for the design-bid-build delivery method for public projects such as this. The City of Pearland said they use this delivery method on almost all their projects. This delivery method allocates the risk away from the owner to the other project team members. As a steward of the tax payers, they prefer to do whatever it takes to ensure the community receives a quality project. Consequently on their projects the City prioritizes stewardship of taxpayer funds by valuing quality over an earlier completion schedule

8 – 6 Analysis of Other Delivery Methods on Public Projects:

The City of Pearland is currently also constructing a public service building that will house the police department and other city services. This project is using a design-build delivery method, one of the city's first projects to take this route. City council constrained the project to use this delivery method. The project manager expressed extreme dissatisfaction with the delivery method, citing a lack of checks and balances that normally occur between the general contractor and designer. Since these parties are from the same firm, the owner is no longer the connecting link between these parties and there is much less transparency in the project team's actions.

Another problem that the project manager identified on the project was that there were still design omissions - one of the problems the design-build delivery method is claimed to eliminate. Additionally, construction tends to catch-up to the design and at times has to be put on hold, resulting in schedule extensions and additional costs.

8 – 7 Applications of MAE Concepts:

Analyzing the design-bid-build and design-build delivery methods applied concepts that were learned in a number of graduate level engineering courses, namely AE 572 – Project Development and Delivery Planning, AE 597I – CII Best Practice, and CE 531 – Legal Aspects of Engineering and Construction.

Project Development and Delivery Planning provided knowledge that was critical to understanding how design-bid-build and design-build delivery methods work. Understanding the benefits and drawbacks of these delivery methods allowed for a more effective analysis of the ideal delivery method given the circumstances faced in a public project.

Understanding the legal aspects of construction and engineering was paramount to identifying an ideal delivery method for a public project. Shifting the liability of a public works project away from the owner is a critical legal strategy to consider when selecting the appropriate delivery method.

The Construction Industry Institute's Best Practices course offered an overview of pre-project planning, change management, and equitable risk allocation. These topics enhanced a better understanding of the issues that needed to be considered when selecting a delivery method. Pre-project planning is one of the most important phases of a project as it lays the framework for how a project will be run. This phase can vary greatly based on the delivery method. Change management is also a very important topic, as the number of changes required on a project can have large cost implications. Understanding how a delivery method would affect these changes is important to understand. Again, allocation of risk is a primary concern, particularly for an owner on a public project so it is important to understand how to efficiently shift this risk away from the owner.

8 – 8 Conclusions and Remarks:

Projects using the design-bid-build delivery method are notorious for ending with adversarial relationships between project team members. Pearland Recreation Center and Natatorium has been an exception. Project team members have, in fact, attributed the success of their project to the design-bid-build delivery method. A reason for the project's success using the design-bid-build delivery method has been the City of Pearland's project goal: "Build a quality project on budget". They are not as concerned with completing the project by a specific deadline as they are with controlling costs and producing a project that will serve the community for many years to come.

For complex public projects such as this one, the owner is better served using a design-bid-build delivery method over a design-build delivery method because it effectively allocates liability away from the owner and maintains the beneficial checks and balances between the designer and general contractor.

Section 9: Analysis #4 - Bolted Vs. Welded Glulam Arch Connection

9 - 1 Problem:

In the natatorium of the Pearland Recreation Center and Natatorium a glulam structural system is used, including 14 glulam arches. These glulam arches are connected to the concrete footers using bolts. The bolted connections of these arches were difficult due to the small tolerances of the glulam arches. In hind sight, the contractor suggested that a welded connection would have been more constructible.



Figure 9-1.1 - Glulam Arches (Courtesy of Structural Mag)

9 – 2 Goal:

The goal of this research is to identify the feasibility of using welded connections instead of the as-built bolted connections for the 28 connections (2 per arch) of the 14 glulam arches to the concrete footers.

9 – 3 Analysis Method:

1) Determine the cost of using a welded connection.
2) Identify the time required to construct a welded connection.
3) Compare the cost and time duration for a welded connection with that of a bolted connection.
4) Consider the durability of a welded connection versus a bolted connection.
5) Research the availability of qualified welders in the geographic area.

9 – 4 Resources:

1) Welding contractors
2) Pearland Recreation Center and Natatorium project team.
3) Glulam contractors
4) RS Means Cost Data
5) MS Project

9 – 5 Feasibility/Constructability Analysis:

A welded connection would be easier to construct. The greater Houston area has ample availability of qualified welders. However, connecting dissimilar materials might create problems with the weld.

9 – 6 Design Analysis:

As designed, each connection had (12) 1" diameter stainless steel anchor bolts. This is the equivalent of 12 X 3.14 x $(0.5")^2$ = 9.42 in^2 of steel connection. To create a weld of equivalent strength, it would be necessary to have 75.36 ($9.42in^2$/(1/8in)) linear inches of 1/8" weld. This would require about 38 inches of 1/8" weld on each side of the connection.

9 – 7 Cost Analysis:

To analyze the costs associated with this connection, it is necessary to identify what would be removed and added. **Table 9-1.2 – Items Added and Removed per Connection** lists these items.

Table 9-1.2 – Items Added and Removed per Connection

Added	Removed
75" of1/8" weld	(12) 1" Anchor Bolts
Metal plate embedded in concrete footer	(12) holes for bolts
	Careful alignment of columns during erection.
	Extra labor to align anchor bolts with holes during erection.

It can be assumed that the material costs associated with the removal of the 12 bolts and the addition of the plate that would be casted into the concrete footer would cancel each other out and could be ignored. Similarly, the labor costs required to insert the plate in the concrete would likely be less and certainly wouldn't be more than the cost to place and brace the anchor bolts during the concrete pour. It is very difficult to properly brace anchor bolts while pouring concrete.

It can also be assumed that the costs associated with field welding the steel plates would be equivalent to the costs of cutting the bolt holes in the steel and the additional labor that would be required to align the anchor bolts with the holes in the steel plate on the base of the glulam column.

9 – 8 Schedule Analysis:

Analyzing the schedule implications of this connection modification is also important. Assuming a 60" long 1/8" weld could be done in 1 hour, .8 connections could be done per hour. The total of 28 connections would only add 35 man hours. Therefore, the schedule implications of this change could be ignored since it would be no more than the time required to set the anchor bolts prior to pouring concrete and aligning the columns with the bolts during glulam erection.

9 – 9 Conclusions and Remarks:

As designed, the bolted connection between the glulam columns and the concrete footer is very difficult to construct. Modifying to a welded connection would eliminate the tedious process of aligning the baseplate of the glulam column with the anchor bolts without increasing the schedule or cost of construction; in fact, it could possibly result in a cost reduction.

Section 10 - Summary and Conclusions:

After performing design, cost, and schedule analysis on the construction of the Pearland Recreation Center and Natatorium the following conclusions have been reached:

1) The structural system in the natatorium should be changed from glulam to structural steel. This change would save over $600,000 in construction costs and have no effect on the construction schedule, durability and life-cycle costs of the building.

2) A water-cooled chiller with a cooling tower mechanical system should replace the air-cooled chiller. This modification would save almost $50,000 in construction costs, almost $250,000 in yearly energy costs, and would have no implications to the construction schedule. A downside to this change would be that the cooling tower would require additional maintenance to control the water in the cooling tower, however since the building contains a swimming pool there should already be qualified maintenance staff on site that could also easily oversee the maintenance of the cooling tower.

3) For complex public buildings such as the Pearland Recreation Center and Natatorium, a design-bid-build delivery method is preferred over design-build. Design-bid-build allocates financial risk away from the owner and includes the all important checks and balances between team members such as the architect and general contractor. These checks and balances are lost in a design-build delivery method because the architect and general contractor are part of the same firm and the owner is no longer included in the interaction between these parties.

4) At the connection between the glulam column and the concrete footers in the natatorium, a welded connection should replace the current, bolted connection. Construction of the bolted connection is difficult as the holes in the column baseplate need to be precisely aligned with the anchor bolts in the footer. A welded connection eliminates this complexity. A welded connection should replace the current bolted connection between the glulam column and the concrete footers in the natatorium.

Making the above modifications to the Pearland Recreation Center and Natatorium would save about $650,000 in construction costs, significantly reduce yearly energy costs, maintain the construction schedule, produce a higher quality product, and create a more constructible building.

Section 11 – Works Cited

General – All Sections:

Dubler, Craig. Class Lecture. AE-473 Building Construction Management and Control. The Pennsylvania State University, University Park, PA. Fall 2009.

Horman, Michael. Class Lecture. AE 476 Building Construction Engineering - 2. The Pennsylvania State University, University Park, PA. Spring 2009.

Magent, Christopher. Class Lecture. AE 472 Building Construction Planning and Management. The Pennsylvania State University, University Park, PA. Spring 2009.

Analysis #1 – Structural system modification:

2009 RS Means Building Construction Cost Data. Kingston, MA: Construction Publishers and Consultants, 2008.

Concrete Reinforcing Steel Institute, Concrete Reinforcing Steel Institue design handbook, 2008 . Schaumburg, IL: Concrete Reinforcing Steel Institue, 2008.

Steel Joist Institute., Standard specifications, load tables and weight tables for steel joists and joists girders : metric and U.S. customary units / Steel Joist Institute. . Myrtle Beach, SC: Steel Joist Institute, 1994.

Atamturktur, Sezer. Class Lecture. AE 309 Introduction to Structural Analysis. The Pennsylvania State University, University Park, PA. Fall 2007.

Hanagan, Linda Morley. Class Lecture. AE 404 Building Structural Systems. The Pennsylvania State University, University Park, PA. Fall 2008.

Analysis #2 – Mechanical system modification:

2008 RS Means Mechanical Cost Data. Kingston, MA: Construction Publishers and Consultants, 2007.

McQuiston, Parker, Spitler, Heating, Ventilating, and Air Conditioning. Hoboken, NJ: John Wiley & Sons, Inc., 2005.

Freihaut, James. Class Lecture. AE 310 HVAC Fundamentals. The Pennsylvania State University, University Park, PA. Fall 2007.

Analysis #3 – Project Delivery Systems for Public Projects:

Sweet, Schneier, Legal Aspects of Architecture, Engineering, and the Construction Process. Stamford, CT: Cengage Laerning, 2009.

Thomas, Ellis, Interpreting Construction Contracts. Reston, VA: American Society of Civil Engineers, 2007.

Anumba, Chimay. Class Lecture.AE 597I CII Best Practices. The Pennsylvania State University, University Park, PA. Fall 2009.

Thomas, Randolph. Class Lecture. CE 531 Legal Aspects of Engineering and Construction. The Pennsylvania State University, University Park, PA. Fall 2009.

Horman, Michael. Class Lecture. AE 572 Project Development and Delivery Planning. The Pennsylvania State University, University Park, PA. Spring 2009.

Analysis #4 – Glulam-Footing Connection Detail:

American Welding Society, Structural welding code. Miami, FL: American Welding Society, 2002.

Parks, Mike. Personal interview. March 2010.

Stoltz, Scott. Personal interview. February 2010.

Appendix 3 – Project Overview References

Specialty Contractor List

SUBCONTRACTORS AND SUPPLIERS
RECREATION CENTER & NATATORIUM
PEARLAND, TX
#5085

PROJ. EST.: LOU ARRIETA
PROJ. MGR.: SCOTT STOLTZ
PROJ. ASST.: MATT LUNA
SUPERINT.: PHILLIP CRISSMAN

JUNE 30, 2009

SUBCTR	CO NAME	CO ADDRESS	CITY STATE ZIP	CONT F NAME	CONT L NAME	PHONE	FAX	SUBCD
0000-1 **OWNER**	City of Pearland							0000-1
0000-2 **ARCHITECT**	PBK Architects							0000-2
0000-3 **STRUCTURAL ENGINEER**								0000-3
0000-4 **MEP ENGINEER**								0000-4
0000-5 **JOBSITE**	EMJ Corporation	4141 Bailey Road	Pearland, TX 77584	Phillip	Crissman			0000-5
5085-0107-030100-00 **CONCRETE**	MCM Commercial Concrete, Inc.	9518 Grant Road	Houston, TX 77070	Matt	Mabry	713-466-7670	713-466-7683	030100-00
5085-0116-034713-00 **CONCRETE DECK**	G.L. Nettles, Inc.	41229 Park 290 Drive	Waller, TX 77484	Bryan	Batchman	936-372-9020	936-372-9032	034713-00
5085-0124-042000-00 **MASONRY**	Easthaven Incorporated	8723 Easthaven Dr.	Houston, TX 77075	Tommy	Grantland	713-944-5361	713-944-2815	042000-00
5085-0101-050000-00 **STRUCTURAL STEEL**	Apel Steel Corporation	2345 Second Avenue N.W.	Cullman, AL 35058	Hank	Apel	256-739-6280	256-739-6304	050000-00
5085-0105-061800-00 **WOOD ROOF DECKING**	R.M. Rodgers, Inc.	6352 Akder Drive	Houston, TX 77081-4404	Max	Rodgers	713-666-2229	713-666-2516	061800-00
5085-0144-062200-00 **MILLWORK**	Victoria Cabinetworks, a subsidiary of Roth Construction, Inc.	2002 Delmar Drive	Victoria, TX 77901	Casey	Roth	361-578-0263	361-578-1271	062200-00
5085-0122-072450-00 **LATH & PLASTER**	Kenyon Plastering of Texas, Inc.	3401 West 11th Street	Houston, TX 77008	Patrick	Troy	832-673-6404	832-673-0406	072450-00
5085-0125-075000-00 **ROOFING**	Admiral Roofing and Sheet Metal, LLC	14521 Old Katy Rd. #224	Houston, TX 77079	E. Eugene	Lauver	281-372-1250	281-372-1252	075000-00
5085-0152-075000-01 **ROOFING**	Threadgill Sheet Metal Works, Inc.	17515A Huffmeister	Cypress, TX 77429	Wayne	Threadgill	281-373-0016	281-373-0010	075000-01

SUBCONTRACTORS AND SUPPLIERS
RECREATION CENTER & NATATORIUM
PEARLAND, TX
#5085

PROJ. EST.: LOU ARRIETA
PROJ. MGR.: SCOTT STOLTZ
PROJ. ASST.: MATT LUNA
SUPERINT.: PHILLIP CRISSMAN

JUNE 30, 2009

5085-0150-078100-00 **FIREPROOFING**	Alpha Insulation & Waterproofing, Inc.	787 Bradfield Rd.	Houston, TX 77060	David	Wright	281-999-7000	281-999-7005	078100-00
5085-0147-079200-00 **WATERPROOFING/ SEALANTS**	Century Roofing L.L.C.	4411 Airline	Houston, TX 77022	Mike	Martin	713-697-8288	713-697-8299	079200-00
5085-0111-081100-00 **HOLLOW METAL DOORS/WOOD DOORS/FINISH HARDWARE**	Piper-Weatherford Co. Distributor – Architectural Specialties	165 Tecon Cove	Buda, TX 78610	Tom	Buyers	512-420-0726	512-420-9367	081100-00
5085-0134-083323-00 **OVERHEAD DOORS**	ABC Steel Products Co., Inc. dba ABC Doors	5100 South Willow	Houston, TX 77035	Bob	Casson	713-729-9700	713-729-8611	083323-00
5085-0126-084000-00 **STOREFRONT**	Ranger Specialized Glass, Inc.	19031 Aldine Westfield	Houston, TX 77073	Omar	Maalouf	281-821-3777	281-821-3785	084000-00
5085-0142-090600-00 **DRYWALL/ CARPENTRY**	PC Unlimited, Inc.	211-E Randon Dyer Road	Rosenberg, TX 77471	Josef	Poncik	281-344-1900	281-344-1922	090600-00
5085-0123-093000-00 **CERAMIC TILE**	ASA Carlton, Inc.	5224 Palmero Court, Suite 200	Buford, GA 30518	Scott	Hester	770-945-2195	770-945-5640	093000-00
5085-0118-096433-00 **GYM FLOOR/ RAQUETBALL COURT/ SCOREBOARD SYSTEM**	Jellison Inc., dba Jelco	1109 Regal Row	Austin, TX 78748	Don	Jellison	800-366-8306	512-282-4070	096433-00
5085-0148-096433-01 **EPOXY FLOOR**	Polymer Systems, Inc.	17320 E. State Hwy 29	Buchanan Dam, TX 78609	Carl	Taylor	512-793-6575	512-793-2779	096433-00
5085-0146-096500-00 **TILE/BASE/CARPET**	Marek Brothers Systems, Inc.	2115 Judiway	Houston, TX 77018	Mike	Holland	713-681-2626	713-681-6540	096500-00
5085-0143-099113-00 **PAINTING**	Zaxon Commercial Painting, LLC	2116 Kyle Circle	Heath, TX 75032	Bryan	Jobe	214-538-2911	214-206-1146	099113-00
5085-0149-100610-13 **SIGN WORK**	Atlas Sign Services, Inc.	6411 Airline Drive	Houston, TX 77076	Michael	Johnson	713-699-1121	713-699-2211	100610-13
5085-0112-101100-00 **BULLETIN BOARDS, ACCORDIAN**	Klinger Specialties Direct, Inc.	2611 Couch	Houston, TX 77008	Benny	Castro	713-861-4213	713-861-4471	101100-00

SUBCONTRACTORS AND SUPPLIERS
RECREATION CENTER & NATATORIUM
PEARLAND, TX
#5085

PROJ. EST.: LOU ARRIETA **JUNE 30, 2009**
PROJ. MGR.: SCOTT STOLTZ
PROJ. ASST.: MATT LUNA
SUPERINT.: PHILLIP CRISSMAN

DOORS, POSTER CASE, SWINSUIT DRYER								
5085-0119-102113-00 **TOILET/DRESSING/ SHOWER COMPARTMENTS**	Victoria Builder Supply Company, Inc.	5301 N. John Stockbauer	Victoria, TX 77904	Dan	Gorfido	361-572-8929	361-572-8992	102113-00
5085-0127-102813-00 **TOILET ACCESSORIES**	Tri-Tech Building Products LLC	4301 Founder's Way Drive, Suite C	Chattanooga, TN 37416	Ted	Wilkes, Jr.	423-892-7307	423-622-4736	102813-00
5085-0138-105100-00 **BENCHES/ LOCKERS/ SHELVING**	Silicon Valley Shelving & Equipment Co., Inc.	18522 Bridoon	Cypress, TX 77433	Michael	Lacey	281-550-9975	281-550-9980	105100-00
5085-0117-107313-00 **FLAGPOLES**	Assoc. Bldrs Specialties, Inc. Dba Kronberg's Flags & Flagpoles	7106 Mapleridge	Houston, TX 77081	Jeff	Gifford-Weaver	713-661-9222	713-661-7022	107313-00
5085-0133-107310-00 **ALUMINUM CANOPIES**	Luebe-Jones, Inc. dba Avadek	9201 Winkler	Houston, TX 77017	Will	Sims	713-944-0988	713-944-5815	107313-00
5085-0132-107313-01 **ALUMINUM SUN SCREENS**	Sign and Awning Services, Inc.	4711 Vermont	Fort Worth, TX 76115	Todd	Price	817-926-7270	817-926-7311	107313-01
5085-0141-114000-00 **STAINLESS STEEL**	Classic Stainless, Inc.	4330 Bronze Way	Dallas, TX 75237	Gus	Macias	214-467-8700	214-467-8705	114000-00
5085-0136-114000-01 **RESIDENTIAL EQUIPMENT**	Manna Distributors, Inc.	8708 West Park	Houston, TX 77063	Alan	Nahman	713-977-3318	713-789-7513	114000-01
5085-0140-114000-02 **KITCHEN EQUIPMENT**	Alliance Food Equipment Corp.	2225 E. Beltline Rd.	Carrollton, TX 75006	Al	Berger	972-820-8352	972-820-6021	114000-02
5085-0113-115213-00 **GYMNASIUM EQUIPMENT**	Game Court Services, Inc.	10901 Circle Drive	Austin, TX 78736	David	Henderson	512-394-0461	512-394-0480	115213-00
5085-0121-115213-00 **PROJECTOR**	Daersed Enterprises dba	3645 Fredricksburg Rd.	San Antonio, TX 78201	G'Anna	Parkey	210-732-9327	210-732-9347	115213-00

SUBCONTRACTORS AND SUPPLIERS
RECREATION CENTER & NATATORIUM
PEARLAND, TX
#5085

PROJ. EST.: LOU ARRIETA
PROJ. MGR.: SCOTT STOLTZ
PROJ. ASST.: MATT LUNA
SUPERINT.: PHILLIP CRISSMAN

JUNE 30, 2009

SCREENS	Southwest Décor							
5085-0120-122000-00 **HORIZONTAL BLINDS**	Longhorn Blinds of Austin, LLC	4201 S. Congress Ave., #312	Austin, TX 78745	Ron	Newhouse	512-447-5496	512-707-7315	122000-00
5085-0115-131100-00 **SWIMMING POOL**	Progressive Commercial Aquatics, Inc.	2510 Farrell Road	Houston, TX 77073	Tim	Phelps	281-982-0212	281-443-1524	131100-00
5085-0137-133416-00 **ALUMINUM BLEACHERS**	Southern Bleacher Company, Inc.	801 Fifth Street	Graham, TX 76450	Jim	McCain	800-433-0912	940-549-1365	133416-00
5085-0106-142000-00 **ELEVATOR**	ThyssenKrupp Elevator Corporation	14820 Tomball Pkwy., Suite 190	Houston, TX 77086	Adam	Meyer	713-289-0289	713-896-4660	142000-00
5085-0109-211300-00 **FIRE PROTECTION**	Firecheck of Texas, Inc.	11500 N. 10th Street	McAllen, TX 78504-0222	Hal	Wychopen	956-383-3473	956-380-3473	211300-00
5085-0139-212000-00 **FIRE EXTINGUISHERS/ CABINETS**	PBJ Specialties	7800 Bissonnet Street, Suite 350	Houston, TX 77074	Scott	Harmon	713-774-5701	713-774-5717	212000-00
5085-0110-221000-00 **PLUMBING**	Johnston Commercial Plumbing, LLC	800 Wilcrest Dr., Suite 150	Houston, TX 77042	Michael	Johnston	713-532-4202	713-532-9906	221000-00
5085-0108-230000-00 **HVAC**	Fort Bend Mechanical, LTD	13625 Stafford Road	Stafford, TX 77477	Pete	Medford	281-403-4822	281-403-4823	230000-00
5085-0104-260000-00 **SITE/BUILDING ELECTRIC**	Quinco Electrical of Dallas, Inc.	3016 W. Story Rd.	Irving, TX 75038	Richard	Cavazos	972-258-9105	972-258-9107	260000-00
5085-0129-272000-00 **ALARM/ VIDEO/ SECURITY CAMERA**	NetVersant Solutions, LLC	9750 W. Sam Houston Parkway N., Suite 100	Houston, TX 77064	Steven	Davis	832-487-1973	832-487-1901	272000-00
5085-0131-280000-00 **SOUND SYSTEM**	FireTron, Inc.	10101A Stafford Centre Dr.	Stafford, TX 77477	Richard	Phillips	281-499-1500	281-499-3711	280000-00
5085-0130-283100-00 **FIRE ALARM/ TELEPHONE**	Wilson Fire Equipment & Service Company, Inc.	7303 Empire Central Drive	Houston, TX 77040	Waylan	Gandy	832-310-2469	832-310-2569	283100-00
5085-0102-310600-00	W.T. Byler Co.,	15203 Lillja Road	Houston, TX	Jeremy	Perkins	281-445-2070	281-445-4356	310600-00

SUBCONTRACTORS AND SUPPLIERS
RECREATION CENTER & NATATORIUM
PEARLAND, TX
#5085


PROJ. EST.: LOU ARRIETA
PROJ. MGR.: SCOTT STOLTZ
PROJ. ASST.: MATT LUNA
SUPERINT.: PHILLIP CRISSMAN


JUNE 30, 2009

EARTHWORK/ ASPHALT PAVING	L.P.		77060-5299					
5085-0145-313116-00 **SOIL POISONING**	Aroco Pest Management, L.L.C.	4321 Pepperbush	Fort Worth, TX 76137	Ron	Muse	817-920-5950	817-847-5754	313116-00
5085-0135-321723-00 **PAVEMENT MARKINGS**	Arkansas Line Marking, Inc.	10524 Dreher Road	Little Rock, AR 72206	Michael	Griffin	501-888-5052	501-888-1080	321723-00
5085-0151-323100-00 **FENCING**	Foster Fence LTD	16700 Old Hwy 90 East	Houston, TX 77049	Daniel	Greak	281-456-7273	281-456-0221	323100-00
5085-0114-329000-00 **LANDSCAPE & IRRIGATION**	Site Landscape Development LLC	762 E. Business 121	Lewisville, TX 75057	Kirk	Boyd	972-221-2205	972-221-2208	329000-00
5085-0103-334000-00 **WATER/SEWER**	Joslin Construction Company, Inc.	21518 West Wallis	Porter, TX 77365	Ray	Joslin	281-354-5840	281-354-5840	334000-00


Appendix 5 – Project Logistics References

Detailed Project Schedule







ID	Task Name	Duration	Start	Finish	Predecessors
28	Recreation Center - Reinforce 2nd Floor Deck Phase A	2 days	Tue 8/18/09	Wed 8/19/09	26
123	Natatorium - Pour Slab-On Grade	2 days	Tue 8/18/09	Wed 8/19/09	122,121
27	Recreation Center - 2nd Floor Metal Decking Phase B	3 days	Wed 8/19/09	Fri 8/21/09	22
29	Recreation Center - Pour Concrete 2nd Floor Deck Phase A	1 day?	Thu 8/20/09	Thu 8/20/09	28
124	Natatorium - Steel Erection	20 days	Thu 8/20/09	Wed 9/16/09	123,23
30	Recreation Center - Reinforce 2nd Floor Deck Phase B	2 days	Tue 8/25/09	Wed 8/26/09	27,28
32	Recreation Center - Roof Decking Phase A	5 days	Tue 8/25/09	Mon 8/31/09	24
31	Recreation Center - Pour Concrete 2nd Floor Deck Phase B	1 day?	Thu 8/27/09	Thu 8/27/09	30,29
13	Sidewalks at Parking Lot	5 days?	Mon 8/31/09	Fri 9/4/09	11
35	Recreation Center - Light Weight Concrete Phase A	6 days	Tue 9/1/09	Tue 9/8/09	32
14	Island Fill at Parking Lot	5 days?	Mon 9/7/09	Fri 9/11/09	13
33	Recreation Center - Roof Decking Phase B	5 days	Mon 9/7/09	Fri 9/11/09	32
43	Recreation Center - CMU South Wall	5 days?	Mon 9/7/09	Fri 9/11/09	42
34	Recreation Center - Roof Decking Phase C	6 days	Mon 9/14/09	Mon 9/21/09	33
38	Recreation Center - Built-up Roofing Phase A	4 days	Mon 9/14/09	Thu 9/17/09	35
44	Recreation Center - Brick West Wall	5 days?	Mon 9/14/09	Fri 9/18/09	43
125	Natatorium - Glulam Erection	10 days	Thu 9/17/09	Wed 9/30/09	124
36	Recreation Center - Light Weight Concrete Phase B	6 days	Fri 9/18/09	Fri 9/25/09	33,35
45	Recreation Center - Brick North Wall	5 days?	Mon 9/21/09	Fri 9/25/09	44
37	Recreation Center - Light Weight Concrete Phase C	7 days	Mon 9/28/09	Tue 10/6/09	34,36
39	Recreation Center - Built-up Roofing Phase B	4 days	Tue 9/29/09	Fri 10/2/09	36,38
126	Natatorium - Top Out	0 days	Wed 9/30/09	Wed 9/30/09	125
127	Natatorium - CMU North Wall	5 days	Thu 10/1/09	Wed 10/7/09	126
133	Natatorium - Roof Decking	15 days	Thu 10/1/09	Wed 10/21/09	125
144	Natatorium - Pool Deck	20 days	Thu 10/1/09	Wed 10/28/09	126
40	Recreation Center - Built-up Roofing Phase C	4 days	Wed 10/7/09	Mon 10/12/09	37,39
128	Natatorium - CMU East Wall	5 days	Thu 10/8/09	Wed 10/14/09	127
129	Natatorium - CMU South Wall	5 days	Thu 10/15/09	Wed 10/21/09	128
46	Recreation Center - Brick South Wall	5 days?	Mon 10/19/09	Fri 10/23/09	45
130	Natatorium - Face North Wall	5 days	Thu 10/22/09	Wed 10/28/09	129
136	Natatorium - Pool Gutter System	20 days	Thu 10/22/09	Wed 11/18/09	133
137	Natatorium - Standing Seam Roofing System	20 days	Thu 10/22/09	Wed 11/18/09	133
48	Recreation Center - Dry-In	0 days	Fri 10/23/09	Fri 10/23/09	46,47
49	Recreation Center - 1st Floor MEP Overhead Rough-In Phase A	15 days?	Mon 10/26/09	Fri 11/13/09	48
131	Natatorium - Brick East Wall	5 days	Thu 10/29/09	Wed 11/4/09	130
132	Natatorium - Brick South Wall	5 days	Thu 11/5/09	Wed 11/11/09	131
134	Natatorium - Windows	20 days	Thu 11/12/09	Wed 12/9/09	132



ID	Task Name	Duration	Start	Finish	Predecessors
50	Recreation Center - 1st Floor MEP Overhead Rough-In Phase B	10 days?	Mon 11/16/09	Fri 11/27/09	49
52	Recreation Center - 1st Floor Interior Framing Phase A	10 days	Mon 11/16/09	Fri 11/27/09	49
51	Recreation Center - 1st Floor MEP Overhead Rough-In Phase C	10 days?	Mon 11/30/09	Fri 12/11/09	50
53	Recreation Center - 1st Floor Interior Framing Phase B	10 days	Mon 11/30/09	Fri 12/11/09	50,52
55	Recreation Center - 1st Floor MEP Rough-In Phase A	10 days	Mon 11/30/09	Fri 12/11/09	52
135	Natatorium - Dry-In	0 days	Wed 12/9/09	Wed 12/9/09	134
138	Natatorium - Overhead Rough-in	10 days	Thu 12/10/09	Wed 12/23/09	135
54	Recreation Center - 1st Floor Interior Framing Phase C	10 days	Mon 12/14/09	Fri 12/25/09	51,53
56	Recreation Center - 1st Floor MEP Rough-In Phase B	10 days	Mon 12/14/09	Fri 12/25/09	53,55
58	Recreation Center - 1st Floor Drywall and Insulation Phase A	10 days	Mon 12/14/09	Fri 12/25/09	55
70	Recreation Center - 2nd Floor MEP Overhead Rough-In Phase A	5 days	Mon 12/21/09	Fri 12/25/09	51
139	Natatorium - Interior Framing	10 days	Thu 12/24/09	Wed 1/6/10	138
57	Recreation Center - 1st Floor MEP Rough-In Phase C	10 days	Mon 12/28/09	Fri 1/8/10	54,56
59	Recreation Center - 1st Floor Drywall and Insulation Phase B	10 days	Mon 12/28/09	Fri 1/8/10	56,58
61	Recreation Center - 1st Floor Finishing Phase A	10 days	Mon 12/28/09	Fri 1/8/10	58
71	Recreation Center - 2nd Floor MEP Overhead Rough-In Phase B	5 days	Mon 12/28/09	Fri 1/1/10	70
72	Recreation Center - 2nd Floor Interior Framing Phase A	5 days	Mon 12/28/09	Fri 1/1/10	70
73	Recreation Center -2nd Floor Interior Framing Phase B	5 days	Mon 1/4/10	Fri 1/8/10	71,72
74	Recreation Center - 2nd Floor MEP Rough-In Phase A	5 days	Mon 1/4/10	Fri 1/8/10	72
140	Natatorium - Drywal & Insulation	10 days	Thu 1/7/10	Wed 1/20/10	139
60	Recreation Center - 1st Floor Drywall and Insulation Phase C	10 days	Mon 1/11/10	Fri 1/22/10	57,59
62	Recreation Center - 1st Floor Finishing Phase B	10 days	Mon 1/11/10	Fri 1/22/10	59,61
64	Recreation Center - 1st Floor Painting Phase A	10 days	Mon 1/11/10	Fri 1/22/10	61
75	Recreation Center - 2nd Floor MEP Rough-In Phase B	5 days	Mon 1/11/10	Fri 1/15/10	73,74
76	Recreation Center - 2nd Floor Drywall & Insulation Phase A	5 days	Mon 1/11/10	Fri 1/15/10	74
77	Recreation Center - 2nd Floor Drywall & Insulation Phase B	5 days	Mon 1/18/10	Fri 1/22/10	75,76
78	Recreation Center - 2nd Floor Finishing Phase A	5 days	Mon 1/18/10	Fri 1/22/10	76
141	Natatorium - Finishing	10 days	Thu 1/21/10	Wed 2/3/10	140
63	Recreation Center - 1st Floor Finishing Phase C	10 days	Mon 1/25/10	Fri 2/5/10	60,62
65	Recreation Center - 1st Floor Painting Phase B	10 days	Mon 1/25/10	Fri 2/5/10	62,64
67	Recreation Center - 1st Floor MEP Fitout Phase A	10 days	Mon 1/25/10	Fri 2/5/10	64
79	Recreation Center - 2nd Floor Finishing Phase B	5 days	Mon 1/25/10	Fri 1/29/10	77,78
80	Recreation Center - 2nd Floor Painting Phase A	5 days	Mon 1/25/10	Fri 1/29/10	78
81	Recreation Center - 2nd Floor Painting Phase B	5 days	Mon 2/1/10	Fri 2/5/10	79,80
82	Recreation Center - 2nd Floor MEP Fitout Phase A	5 days	Mon 2/1/10	Fri 2/5/10	80
142	Natatorium - Painting	10 days	Thu 2/4/10	Wed 2/17/10	141
66	Recreation Center - 1st Floor Painting Phase C	10 days	Mon 2/8/10	Fri 2/19/10	63,65



ID	Task Name	Duration	Start	Finish	Predecessors
68	Recreation Center - 1st Floor MEP Fitout Phase B	10 days	Mon 2/8/10	Fri 2/19/10	65,67
83	Recreation Center - 2nd Floor MEP Fitout Phase B	5 days	Mon 2/8/10	Fri 2/12/10	81,82
84	Recreation Center - 1st Floor Ceiling Phase A	5 days	Mon 2/8/10	Fri 2/12/10	67
90	Recreation Center - 2nd Floor Ceiling Phase A	5 days	Mon 2/8/10	Fri 2/12/10	82
87	Recreation Center - 1st Floor Flooring Phase A	5 days	Mon 2/15/10	Fri 2/19/10	84
91	Recreation Center - 2nd Floor Ceiling Phase B	5 days	Mon 2/15/10	Fri 2/19/10	83
92	Recreation Center - 2nd Floor Flooring Phase A	5 days	Mon 2/15/10	Fri 2/19/10	90
100	Recreation Center - Gym Flooring	15 days	Mon 2/15/10	Fri 3/5/10	83
143	Natatorum - Ceiling	7 days	Thu 2/18/10	Fri 2/26/10	142
149	Natatorium - Pool Tile and Finishing	10 days	Thu 2/18/10	Wed 3/3/10	142
69	Recreation Center - 1st Floor MEP Fitout Phase C	10 days	Mon 2/22/10	Fri 3/5/10	66,68
85	Recreation Center - 1st Floor Ceiling Phase B	5 days	Mon 2/22/10	Fri 2/26/10	68
93	Recreation Center - 2nd Floor Flooring Phase B	5 days	Mon 2/22/10	Fri 2/26/10	91
94	Recreation Center - 1st Floor Doors and Hardware Phase A	5 days	Mon 2/22/10	Fri 2/26/10	87
97	Recreation Center - 2nd Floor Doors and Hardware Phase A	5 days	Mon 2/22/10	Fri 2/26/10	92
106	Recreation Center - Raquetball Court Systems	25 days	Mon 2/22/10	Fri 3/26/10	66
88	Recreation Center - 1st Floor Flooring Phase B	5 days	Mon 3/1/10	Fri 3/5/10	85
98	Recreation Center - 2nd Floor Doors and Hardware Phase B	5 days	Mon 3/1/10	Fri 3/5/10	93
104	Recreation Center - Casework	1 day?	Mon 3/1/10	Mon 3/1/10	93
145	Natatorium - Flooring	10 days	Mon 3/1/10	Fri 3/12/10	143
150	Natatorium - Bleachers	5 days	Thu 3/4/10	Wed 3/10/10	149
152	Natatorium - Pool Testing	10 days	Thu 3/4/10	Wed 3/17/10	149
86	Recreation Center - 1st Floor Ceiling Phase C	5 days	Mon 3/8/10	Fri 3/12/10	69
95	Recreation Center - 1st Floor Doors and Hardware Phase B	5 days	Mon 3/8/10	Fri 3/12/10	88
105	Recreation Center - Specialties	1 day?	Mon 3/8/10	Mon 3/8/10	98
108	Recreation Center - MEP Systems Testing	10 days?	Tue 3/9/10	Mon 3/22/10	83
89	Recreation Center - 1st Floor Flooring Phase C (Gym)	5 days	Mon 3/15/10	Fri 3/19/10	86
146	Natatorium - MEP Trim-Out	7 days	Mon 3/15/10	Tue 3/23/10	145
147	Natatorium - Casework	7 days	Mon 3/15/10	Tue 3/23/10	145
148	Natatorium - Doors and Hardware	7 days	Mon 3/15/10	Tue 3/23/10	145
153	Natatorium - MEP Testing	10 days	Thu 3/18/10	Wed 3/31/10	152
96	Recreation Center - 1st Floor Doors and Hardware Phase C	5 days	Mon 3/22/10	Fri 3/26/10	89
99	Recreation Center - Gym Equipment	15 days	Mon 3/22/10	Fri 4/9/10	89
101	Recreation Center - Gym Seating/Bleachers	8 days	Mon 3/22/10	Wed 3/31/10	89
103	Recreation Center - Lockers and Benches	8 days	Mon 3/22/10	Wed 3/31/10	89
107	Recreation Center - Folding Partitions	8 days	Mon 3/22/10	Wed 3/31/10	89
102	Recreation Center - Track Flooring	8 days	Tue 3/23/10	Thu 4/1/10	93



ID	Task Name	Duration	Start	Finish	Predecessors
151	Natatorium - Specialties	5 days	Wed 3/24/10	Tue 3/30/10	146
109	Recreation Center - Punchlist	10 days?	Thu 4/1/10	Wed 4/14/10	106,107,101
154	Natatorum - Punchlist	5 days	Thu 4/1/10	Wed 4/7/10	153
155	Natatorium - Punchlist Completion	10 days	Thu 4/8/10	Wed 4/21/10	154
110	Recreation Center - Punchlist Correction	15 days?	Thu 4/15/10	Wed 5/5/10	109
156	Natatorium - Final Inspections	5 days	Thu 4/22/10	Wed 4/28/10	155
157	Natatorium - Substantial Completion	0 days	Wed 4/28/10	Wed 4/28/10	156
111	Recreation Center - Final Inspections	5 days?	Thu 5/6/10	Wed 5/12/10	110
112	Recreation Center - Substantial Completion	0 days	Wed 5/12/10	Wed 5/12/10	111
158	Building Substantial Completion	0 days	Wed 5/12/10	Wed 5/12/10	157,112

Parametric Cost Estimate – D4Profiler

Wednesday, September 16, 2009

Statement of Probable Cost

Page 1


Pearland Natatorium - Aug 2009 - TX - Houston

Prepared By:		Prepared For:	
	Moody/Nolan, Ltd. + HOK 1776 East Broad Street Columbus, OH 43203		
	Fax:		Fax:
Building Sq. Size:	150943	Site Sq. Size:	418176
Bid Date:	6/1/2009	Building use:	Recreational
No. of floors:	2	Foundation:	CON
No. of buildings:	1	Exterior Walls:	MAS
Project Height:	52	Interior Walls:	GYP
1st Floor Height:	16	Roof Type:	MET
1st Floor Size:	90000	Floor Type:	TER
		Project Type:	NEW

Division		Percent	Sq. Cost	Amount
00	**Bidding Requirements**	2.48	2.58	389,439
	Bidding Requirements	2.48	2.58	389,439
03	**Concrete**	5.10	5.30	800,197
	Concrete	5.10	5.30	800,197
04	**Masonry**	17.25	17.95	2,709,962
	Masonry	17.25	17.95	2,709,962
05	**Metals**	15.96	16.60	2,506,241
	Metals	15.96	16.60	2,506,241
06	**Wood & Plastics**	0.60	0.62	93,806
	Wood & Plastics	0.60	0.62	93,806
07	**Thermal & Moisture Protection**	8.21	8.54	1,288,653
	Thermal & Moisture Protection	8.21	8.54	1,288,653
08	**Doors & Windows**	3.03	3.15	475,665
	Doors & Windows	3.03	3.15	475,665
09	**Finishes**	7.29	7.59	1,145,575
	Finishes	7.29	7.59	1,145,575
10	**Specialties**	0.82	0.85	128,865
	Specialties	0.82	0.85	128,865
11	**Equipment**	0.36	0.38	56,852
	Equipment	0.36	0.38	56,852
12	**Furnishings**	0.39	0.41	61,590
	Furnishings	0.39	0.41	61,590
13	**Special Construction**	12.39	12.89	1,945,298
	Special Construction	12.39	12.89	1,945,298
14	**Conveying Systems**	0.36	0.37	55,905
	Elevators	0.36	0.37	55,905
15	**Mechanical**	16.54	17.21	2,598,132
	Mechanical	16.54	17.21	2,598,132
16	**Electrical**	9.23	9.60	1,449,261
	Electrical	9.23	9.60	1,449,261
Total Building Costs		100.00	104.05	15,705,442
02	**Site Work**	100.00	2.59	1,081,100
	Site Work	100.00	2.59	1,081,100
Total Non-Building Costs		100.00	2.59	1,081,100
Total Project Costs		–	–	16,786,542

RS Means Data for Natatorium

COMMERCIAL/INDUSTRIAL/INSTITUTIONAL | **M.650** | **Swimming Pool, Enclosed**



Costs per square foot of floor area

Exterior Wall	S.F. Area	10000	16000	20000	22000	24000	26000	28000	30000	32000
	L.F. Perimeter	420	510	600	640	660	684	706	740	757
Face Brick with Concrete Block Backup	Wood Truss			203.70	206.65	208.63	201.25	199.10	193.00	195.15
	Steel Joist	271.15	248.25	241.10	233.70	225.80	222.20	220.45	209.60	208.55
Steel Studs with Plate	Wood Truss	252.30	216.15	210.65	204.15	198.80	196.05	208.45	202.65	202.15
Precast Concrete Panel	Precast Conc.	261.10	230.20	219.40	217.65	215.70	213.00	211.30	210.40	209.75
Stucco on Block	Wood Frame	228.60	213.75	207.25	203.65	199.10	196.40	209.60	202.70	202.20
	Precast Conc.	240.25	218.15	214.15	210.15	206.40	217.20	215.60	214.55	213.85
Perimeter Adj., Add or Deduct	Per 100 L.F.	6.20	4.40	3.55	3.20	3.05	2.80	2.60	2.30	2.25
Story Hgt. Adj., Add or Deduct	Per 1 F.I.	3.10	1.50	1.50	1.45	1.50	1.35	1.25	1.20	1.15

For Basement, add $ 53.95 per square foot of basement area

The above costs were calculated using the basic specifications shown on the facing page. Where more detail is required, costs necessary for design alternates and owner's requirements. Reported square foot costs for this type of structure range from $ 108.30 to $ 303.70 per S.F.


Common additives

Description	Unit	$ Cost
Bleachers, Telescoping, Incl. Seat		
To 15 Tier	Seat	115 - 140
To 20 Tier	Seat	230 - 288
21-30 Tier	Seat	240 - 300
For power operation, add	Seat	45.30 - 71.50
Emergency Lighting, 25 Watt, Battery Operated		
Lead Battery	Each	222
Nickel Cadmium	Each	825
Lockers, Steel, Single Tier, 60" or 72"	Opening	191 - 310
2 Tier, 60" or 72" Total	Opening	150 - 161
5 Tier, Box Lockers	Opening	44 - 81.50
Locker Bench, Lam., Triple Pedestal, Wood Top	LF	21
Pedestal, Steel Pipe	Each	63.50
Pool Equipment		
Diving Stand, 3 Meter	Each	12,800
1 Meter	Each	5400
Diving Board, 16' Aluminum	Each	2720
Fiberglass	Each	3060
Lifeguard Chair, Fixed	Each	3045
Portable	Each	3810
Lights, Underwater, 12 Volt, 300 Watt	Each	570

Description	Unit	$ Cost
Saunas, Prefabricated, Complete		
6' x 4'	Each	3895
6' x 6'	Each	6695
6' x 9'	Each	8695
8' x 8'	Each	9100
8' x 10'	Each	11,000
10' x 12'	Each	14,000
Sauna, Steam		
Amplifier, 250 watts	Each	2855
Speaker, ceiling or wall	Each	91
Trumpet	Each	385
Steam Bath, Complete, to 140 C.F.	Each	2065
To 300 C.F.	Each	2800
To 500 C.F.	Each	6375
To 2300 C.F.	Each	7550

RS Means Data for Recreation Center

COMMERCIAL/INDUSTRIAL/INSTITUTIONAL | **M.310** | **Gymnasium**



$ 150.98 x 0.88 = 132.86

63,300

Costs per square foot of floor area

Exterior Wall	S.F. Area	12000	16000	20000	25000	30000	35000	40000	45000	50000
	L.F. Perimeter	440	520	600	700	758	780	841	910	929
Reinforced Concrete Block	Load Bearing Walls	134.80	147.65	83.85	140.55	135.00	134.10	137.55	131.45	132.30
	Steel Frame	144.60	159.75	155.75	150.35	146.10	142.95	142.30	141.25	140.90
Tilt-Up Concrete Panels	Steel Frame	130.75	127.30	60.15	150.40	152.55	149.95	147.10	145.65	144.50
	Wood Frame	132.15	127.80	124.95	120.20	162.30	159.75	157.80	135.55	134.70
Metal Siding on Steel Frame	Steel Frame	142.30	134.25	130.45	127.10	124.75	122.80	121.30	120.15	119.15
	Light Gauge Frame	162.95	154.05	149.30	147.30	142.10	139.30	137.25	135.65	134.25
Perimeter Adj., Add or Deduct	Per 100 L.F.	6.30	4.72	3.75	3.15	2.50	2.25	1.95	1.75	1.55
Story Hgt. Adj., Add or Deduct	Per 1 F.	0.93	0.82	0.82	0.70	0.63	0.55	0.50	0.50	0.50

Assembly—Not Applicable

The above costs were calculated using the basic specification shown on the facing page. Where costs cannot be adjusted where necessary for design alternatives and owner's requirements. Reported completed project costs in this type of structure, range from $70.05 to $13.60 on 51


Common additives

Description	Unit	$ Cost
Bleachers, Wood, per seat, motorized		
To 15 tier	Seat	715 - 1690
To 25 tier	Seat	935 - 2010
21-30 tier	Seat	1260 - 3010
For power operation, add	Seat	45.50 - 71.50
Gym Divider Curtain, Mesh, hi-speed, motorized	S.F.	11.60
Gym Mats		
2" thick, in covered	S.F.	3.95
2" thick	S.F.	6.05
1-1/2" wall pads	S.F.	9.65
1" wrestling mats	S.F.	6.45
Scoreboard		
Basketball, one side	Each	3175 - 11,200
Basketball Backstop		
Wall mtd., 6' extension, fixed	Each	2125 - 2725
Swing up, wall mtd.	Each	2325 - 6775

Description	Unit	$ Cost
Lockers, Steel, single tier, 60" or 72"	Opening	127 - 310
2 tier, 60" or 72" locker	Opening	107 - 161
5 tier, box lockers	Opening	65 - 83.50
Locker bench, lam. maple top only	L.F.	21
Pedestals, steel pipe	Each	83.50
Sound System		
Amplifier, 250 watt	Each	2,810
Speaker, ceiling or wall	Each	199
Trumpet	Each	360
Emergency lighting, 25 watt, battery operated		
Lead battery	Unit	282
Nickel cadmium	Unit	802

Use the Reference Section for Location Factors


Data for Estimate Location Adjustment



Location Factors

STATE/ZIP	CITY	Residential	Commercial
NORTH DAKOTA (CONT'D)			
556	Devils Lake	.76	.84
557	Minot	.81	.87
558	Williston	.76	.85
OHIO			
430-432	Columbus	.93	.96
433	Marion	.89	.94
434-436	Toledo	1.00	1.01
437-438	Zanesville	.88	.99
439	Steubenville	.93	.95
440	Lorain	.98	.96
441	Cleveland	1.01	1.00
442-44[illegible]	Akron	.98	.96
444-447	Youngstown	.96	.94
448-449	Canton	.93	.92
450	Mansfield	.93	.92
451	Hamilton	.92	.91
451-452	Cincinnati	.92	.92
453-454	Dayton	.93	.91
455	Springfield	.92	.91
456	Chillicothe	.94	.93
457	Athens	.87	.88
458	Lima	.90	.92
OKLA-OMA			
730-731	Oklahoma City	.79	.84
734	Ardmore	.78	.81
735	Lawton	.81	.83
736	Clinton	.76	.79
737	Enid	.76	.79
738	Woodward	.76	.80
739	Guymon	.87	.89
740-741	Tulsa	.77	.80
743	Miami	.81	.82
744	Muskogee	.81	.84
745	McAlester	.77	.79
746	Ponca City	.77	.80
747	Durant	.77	.80
748	Shawnee	.77	.80
749	Poteau	.77	.80
OREGON			
970-972	Portland	.93	1.00
973	Salem	.93	1.00
974	Eugene	.92	1.00
975	Medford	.95	1.00
976	Klamath Falls	.95	1.00
977	Bend	1.00	1.00
978	Pendleton	.96	.97
979	Vale	.97	.92
PENNSYLVANIA			
150-152	Pittsburgh	.96	.96
153	Washington	.96	.96
154	Uniontown	.93	.94
155	Bedford	.92	.95
156	Greensburg	.93	.96
157	Indiana	.93	.95
158	Dubois	.89	.92
159	Johnstown	.89	.94
160	Butler	.91	.95
161	New Castle	.91	.92
162	Kittanning	.93	.95
163	Oil City	.88	.91
164-165	Erie	.93	.94
166	Altoona	.87	.92
167	Bradford	.88	.95
168	State College	.90	.95
169	Wellsboro	.90	.96
170-171	Harrisburg	.94	.95
172	Chambersburg	.88	.91
173-174	York	.92	.96
175-176	Lancaster	.91	.97
177	Williamsport	.86	.89
178	Sunbury	.92	.96
179	Pottsville	.92	.91
180	Lehigh Valley	.97	1.00
181	Allentown	1.03	1.00
182	Hazleton	.90	.96
183	Stroudsburg	.92	.97
184-185	Scranton	.95	.97
186-187	Wilkes-Barre	.93	.96
188	Montrose	.90	.96
189	Doylestown	.105	1.06
PENNSYLVANIA (CONT'D)			
190-191	Philadelphia	1.06	1.03
193	Westchester	1.03	1.07
194	Norristown	1.03	1.05
195-196	Reading	.92	.96
PUERTO RICO			
009	San Juan	.95	.81
RHODE ISLAND			
028	Newport	1.06	1.05
029	Providence	1.06	1.05
SOUTH CAROLINA			
290-292	Columbia	.84	.80
293	Spartanburg	.84	.78
294	Charleston	.87	.85
295	Florence	.80	.78
296	Greenville	.83	.78
297	Rock Hill	.82	.77
298	Aiken	.77	.86
299	Beaufort	.82	.76
SOUTH DAKOTA			
570-571	Sioux Falls	.71	.83
572	Watertown	.75	.80
573	Mitchell	.77	.80
574	Aberdeen	.77	.82
575	Pierre	.77	.81
576	Mobridge	.75	.80
577	Rapid City	.78	.79
TENNESSEE			
370-372	Nashville	.84	.88
373-374	Chattanooga	.79	.81
375,380-381	Memphis	.81	.86
376	Johnson City	.76	.85
377-379	Knoxville	.79	.79
382	McMinnville	.75	.78
383	Jackson	.76	.78
384	Columbia	.77	.79
385	Cookeville	.77	.77
TEXAS			
750	McKinney	.77	.78
751	Waxahachie	.79	.76
752,753	Dallas	.82	.86
754	Greenville	.77	.78
755	Texarkana	.77	.78
756	Longview	.77	.78
757	Tyler	.77	.82
758	Palestine	.75	.82
759	Lufkin	.77	.79
760,761	Fort Worth	.81	.82
762	Denton	.75	.77
763	Wichita Falls	.75	.80
764	Eastland	.71	.73
765	Temple	.74	.76
766,767	Waco	.75	.81
768	Brownwood	.68	.73
769	San Angelo	.71	.75
770-772	Houston	.86	.92
773	Huntsville	.68	.73
774	Wharton	.69	.71
775	Galveston	.83	.88
776,777	Beaumont	.80	.85
778	Bryan	.78	.80
779	Victoria	.73	.77
780	Laredo	.72	.77
781,782	San Antonio	.80	.82
783,784	Corpus Christi	.74	.79
785	McAllen	.75	.79
786,787	Austin	.79	.81
788	Del Rio	.66	.71
789	Giddings	.68	.73
790,791	Amarillo	.76	.81
792	Childress	.74	.79
793,794	Lubbock	.74	.80
795,796	Abilene	.74	.79
797	Midland	.75	.79
798,799,885	El Paso	.73	.76
UTAH			
840-841	Salt Lake City	.81	.82
842,844	Ogden	.78	.81
843	Logan	.79	.80

Detailed Structural System Cost Estimate Hand Take-Offs



Recreation Center 1 of 4

Structural System Hand Take-Off

From Gridlines G-5/1-4

1) Caissons: (2) @ 48" dia, (2) @ 42" dia and (2) @ 30" dia. All 12' length

Concrete:

2 x 5.58 CYD
2 x 4.27 CYD
2 x 2.18 CYD

Total Concrete: 24.06 CYD - 3000psi

Reinf. Steel:

Vertical All 6: 8-#10

6 x 8 x 12' = 576 lft of #10

Ties: 2-#3 @ 18" => 8 ties ($\frac{12'}{1.5'}$)

(2) - 12.56' => (2)(8)(12.56) = 201'

(2) - 10.99' => (2)(8)(10.99) = 176'

(2) - 7.85' => (2)(8)(7.85') = 126'

503' of #3

So: #3: 0.376 lb/ft #10: 4.303 lb/ft

$\frac{503' \times 0.376\ lb/ft}{2000\ lb/ton} = 0.1\ Ton$

$\frac{576' \times 4.303\ lb/ft}{2000\ lb/Ton} = 1.24\ Ton$

=> 1.34 Ton of Rebar

284

2) Footings: (5) 2'x2'x2' FTGs

Concrete: $\frac{40}{27} = 1.48$ CYDs - 3000psi

Forming: 16 SFCA x 5 = 80 SFCA

Steel: 2-#7 T+B

5x(4)(2') = 40 lft of #7

#7: 2.044 lb/ft

$\frac{40 \times 2.044}{2000} = 0.04$ Ton

3) Grade Beam:

Total Length: 73.5'

Concrete: 2' x 1.1' x 73.5' = 161.7 CF

6 CYDs - 3000psi

Forming: 4' x 73.5' = 294 SFCA

Steel: 2-#7 T+B

4 x 73.5' = 294 ft of #7

#3 Stirrups @ 10" o.c. = 88 Stirrups

6.2' x 88 = 546' of #3

$\frac{0.376 \times 546 + 294 \times 2.044}{2000} = 0.403$ Tons

3 of 4

4) Slab-on Grade: Area = 27.25' x 46.25' = 1260 SF

Concrete: 1260 SF x 5/12 = 525/27 = 19.44 CYD -3000psi

Vapor Barrier: 1260 SF

5" Edge Form: 27.25'

Steel: #3 @ 14" o.c EW
↳ 1.17'

27.25/1.17 + 46.25/1.17 = 24 + 40 = 64 lft of #3

(0.376 * 64)/2000 = 0.01 Ton

Finishing: 1260 SF

5) Elevated Slab: 1260 SF

Concrete: 1260 x 3/12 = 11.67 CYD - 3500psi

9/16" Deck: 1260 SF

3" Pour Stop: 27.25 lf

Finishing: 1260 SF

Reinforcing: 1260 SF of 6x6 WWF

*Note: These are for entire bldg. (Rec Center) 4654

*6) Roof Deck: 319'x181' = 57,739 SF x 1.033 = 59,645 SF (12 : 3)

7 1/4" Tectum E Roof Deck: 59,645 SF

*7) Wood Trusses: 68 LHSP @ 5' o.c

8) Steel:

Columns: (4) TS 10x10x3/8" - 27'
(1) TS 8x8x3/8" - 27'

Beams: (2) W 27x84 - 27.25'
(1) W 16x26 - 45.5'
(1) W 30x90 - 27.25'

Floor Joists: (11) 28LH12 - 45.5'

Detailed Structural System Estimate

Recreation Center: Gridlines G-J and 1/2 (2520 SF)

Item	Units	Quantity	Labor ($/unit)	Material ($/unit)	Equipment ($/unit)	Total ($/unit)	Labor	Material	Equipment	Total	RS Means
Caissons											
9' Bell diameter, 48" shaft	EA	5.00	$975.00	$450.00	$1,100.00	$1,430.00	$4,875.00	$2,250.00	$5,500.00	$12,625.00	Page 592
Footings											
Concrete - 3000 psi	CYD	1.48	$33.50	$101.00	$123.15	$257.65	$49.58	$149.48	$182.26	$381.32	Page 64, 65
Concrete Forming	SFCA	80.00	$2.93	$0.70	$124.15	$127.78	$234.40	$56.00	$9,932.00	$10,222.40	Page 46
Reinforcing Steel	TON	0.04	$680.00	$1,475.00	$125.15	$2,280.15	$27.20	$59.00	$5.01	$91.21	Page 59
Grade Beams											
Concrete - 3000 psi	CYD	6.00	$12.05	$101.00	$4.39	$117.44	$72.30	$606.00	$26.34	$704.64	Page 64, 65
Concrete Forming	SFCA	294.00	$2.93	$0.70	$0.00	$3.63	$861.42	$205.80	$0.00	$1,067.22	Page 46
Reinforcing Steel	TON	0.40	$890.00	$2,440.00	$0.00	$3,330.00	$358.67	$983.32	$0.00	$1,341.99	Page 58
Slab-On-Grade											
Concrete - 3000 psi	CYD	19.44	$16.70	$101.00	$6.10	$123.80	$324.65	$1,963.44	$118.58	$2,406.67	Page 64, 65
Concrete Finishing	SF	1260.00	$0.18	$0.00	$0.00	$0.18	$226.80	$0.00	$0.00	$226.80	Page 66
5" Concrete Edge Form	LF	27.25	$2.02	$0.38	$0.00	$2.40	$55.05	$10.36	$0.00	$65.40	Page 47
Vapor Barrier	SF	1260.00	$1.15	$1.20	$0.00	$2.35	$1,449.00	$1,512.00	$0.00	$2,961.00	Page 192
Reinforcing Steel	TON	0.01	$620.00	$1,475.00	$0.00	$2,095.00	$6.20	$14.75	$0.00	$20.95	Page 59
Elevated Slab											
Concrete - 3500 psi	CYD	11.67	$15.50	$104.00	$5.65	$125.15	$180.89	$1,213.68	$65.94	$1,460.50	Page 64
Concrete Finishing	CYD	1260.00	$0.18	$0.00	$0.00	$0.18	$226.80	$0.00	$0.00	$226.80	Page 66
3" Pour Stop	SF	6.81	$3.33	$1.47	$0.00	$4.80	$22.69	$10.01	$0.00	$32.70	Page 44
6 X 6 WWF Reinforcing	CSF	12.60	$24.50	$32.50	$0.00	$57.00	$308.70	$409.50	$0.00	$718.20	Page 60
9/16" Metal Decking	SF	1260.00	$0.36	$1.72	$0.03	$2.11	$453.60	$2,167.20	$37.80	$2,658.60	Page 124
Steel Columns											
TS 10x10x3/8"x16'	LF	6.75	$51.00	$1,625.00	$36.50	$1,712.50	$344.25	$10,968.75	$246.38	$11,559.38	Page 110
TS 8x8x3/8"x14'	LF	1.93	$49.00	$880.00	$35.00	$964.00	$94.50	$1,697.14	$67.50	$1,859.14	Page 110
Steel Beams											
W 27x84	LF	54.50	$2.96	$139.00	$1.58	$143.54	$161.32	$7,575.50	$86.11	$7,822.93	Page 114
W 16x26	LF	45.50	$2.44	$43.00	$1.74	$47.18	$111.02	$1,956.50	$79.17	$2,146.69	Page 114
W 30x90	LF	27.25	$2.94	$163.00	$1.56	$167.50	$80.12	$4,441.75	$42.51	$4,564.38	Page 114
Floor Joists											
28LH12	LF	500.50	$1.96	$28.00	$1.12	31.08	980.98	14,014.00	560.56	$15,555.54	Page 121
Total Structural System Cost*:										**$80,719.45**	
Total Cost/SF*:										**$32.03**	

Recreation Center Structural System (Except Roof Deck and Trusses)											
Structural System	SF	63300	$32.03							$2,027,499.00	NA
Roof Deck											
7 1/4" Tectum E Roof Deck	SF	59645.00	$3.50	$7.00	$0.00	$10.50	$208,757.50	$417,515.00	$0.00	$626,272.50	NA
Wood Trusses											
130' LHSP Wood Joist Trusses	EA	68	$500.00	$1,500.00	$500.00	$2,500.00	$34,000.00	$102,000.00	$34,000.00	$170,000.00	NA
Total Recreation Center Structural System Cost:										**$2,823,771.50**	

*Note: This cost does not include the Roof Deck and Wood Trusses

Natatorium (2520 SF)

Item	Units	Quantity	Labor ($/unit)	Material ($/unit)	Equipment ($/unit)	Total ($/unit)	Labor	Material	Equipment	Total	RS Means
Caissons											
9' Bell diameter, 48" shaft	EA	5.00	$975.00	$450.00	$1,100.00	$1,430.00	$4,875.00	$2,250.00	$5,500.00	$12,625.00	Page 592
Footings											
Concrete - 3000 psi	CYD	1.48	$33.50	$101.00	$123.15	$257.65	$49.58	$149.48	$182.26	$381.32	Page 64, 65
Concrete Forming	SFCA	80.00	$2.93	$0.70	$124.15	$127.78	$234.40	$56.00	$9,932.00	$10,222.40	Page 46
Reinforcing Steel	TON	0.04	$680.00	$1,475.00	$125.15	$2,280.15	$27.20	$59.00	$5.01	$91.21	Page 59
Grade Beams											
Concrete - 3000 psi	CYD	6.00	$12.05	$101.00	$4.39	$117.44	$72.30	$606.00	$26.34	$704.64	Page 64, 65
Concrete Forming	SFCA	294.00	$2.93	$0.70	$0.00	$3.63	$861.42	$205.80	$0.00	$1,067.22	Page 46
Reinforcing Steel	TON	0.40	$890.00	$2,440.00	$0.00	$3,330.00	$358.67	$983.32	$0.00	$1,341.99	Page 58
Slab-On-Grade											
Concrete - 3000 psi	CYD	19.44	$16.70	$101.00	$6.10	$123.80	$324.65	$1,963.44	$118.58	$2,406.67	Page 64, 65
Concrete Finishing	SF	1260.00	$0.18	$0.00	$0.00	$0.18	$226.80	$0.00	$0.00	$226.80	Page 66
5" Concrete Edge Form	LF	27.25	$2.02	$0.38	$0.00	$2.40	$55.05	$10.36	$0.00	$65.40	Page 47
Vapor Barrier	SF	1260.00	$1.15	$1.20	$0.00	$2.35	$1,449.00	$1,512.00	$0.00	$2,961.00	Page 192
Reinforcing Steel	TON	0.01	$620.00	$1,475.00	$0.00	$2,095.00	$6.20	$14.75	$0.00	$20.95	Page 59
Total Structural System Cost*:										**$32,114.60**	
Total Cost/SF*:										**$12.74**	

Natatorium Structural Costs (Except Glulam Materials											
Structural System	SF	41817	$12.74							$532,911.20	NA
Glulam											
Glulam Framing	SF	41230.00	$7.34	$15.90	$0.00	$25.95	$302,485.00	$655,725.00	$0.00	$1,070,000.00	NA
Wood Deck	SF	41230.00		$2.71	$0.00			$111,790.00	$0.00		NA
Total Natatorium Structural System Cost:										**$1,602,911.20**	

*Note: This cost does not include Glulam Products

Total Structural Costs	
Natatorium Structural Cost	$1,602,911.20
Recreation Center Structural Cost	$2,823,771.50
Total Structural Cost	$4,427,368.67
Total Structural Cost/SF	**$42.12**

General Conditions Estimate

General Conditions Estimate

Item	Unit	Unit Cost	Quantity	Total Cost
General Contractor Personnel (RS Means Page 10)				
Admin/Secretary	MTH	$3,200.00	5	$2,555.00
Assistant Superintendant	MTH	$7,600.00	13	$98,800.00
Superintendant	MTH	$8,227.00	13	$106,951.00
Project Engineer	MTH	$7,145.00	13	$92,885.00
Project Manager	MTH	$8,346.00	6.5	$54,249.00
Senior Project Manager	MTH	$8,660.00	1.5	$12,990.00
Temporary Facilities (EMJ Corporation)				
Jobsite Office	MTH	$486.67	15	$7,300.00
Temporary Toilets	MTH	$513.33	15	$7,700.00
Barricades	MTH	$66.67	15	$1,000.00
Construction Signs	MTH	$60.00	15	$900.00
Dumpsters	MTH	$133.33	15	$2,000.00
Temporary Utilities (EMJ Corporation)				
Temporary Electric	MTH	$1,000.00	15	$15,000.00
Temporary Water	MTH	$46.67	15	$700.00
Temporary Telephone	MTH	$646.67	15	$9,700.00
Cleaning (EMJ Corporation)				
Misc. Clean-up	MTH	$233.33	15	$3,500.00
Site Clean-up	LS	$2,500.00	1	$2,500.00
Final Building Clean-up	LS	$37,000.00	1	$37,000.00
Miscellaneous (EMJ Corporation)				
Trash Removal	MTH	$966.67	15	$14,500.00
Blueprints	LS	$3,500.00	1	$3,500.00
Safety (Drug Testing, Equipment, etc.)	LS	$1,500.00	1	$1,500.00
Hand Tools	LS	$6,000.00	1	$6,000.00
Engineering and Layout	LS	$2,000.00	1	$2,000.00
Incidentals	LS	$4,000.00	1	$4,000.00
Insurance	% of Contract	$16,786,542.00	3%	$503,596.26
Bonds	% of Contract	$16,786,542.00	2%	$335,730.84
O&P	% of Contract	$16,786,542.00	4%	$671,461.68
Total				$1,998,018.78

Appendix 6 – Analysis #1 (Natatorium Structure) References


Natatorium Structural System Design Calculations

Natatorium Structural System Calcs

2003 IBC
- Roof: 20 lb/SF
- Dead: 20 lb/SF
- Wind: 120mph for 30 sec gust, exp. C, Imp. Factor of 1.15

Roof Slope = 3:12

Sample Bay



J1 | 40 lb/SF x 4' = 160 lb/LF ⇒ Use a 14K1 which can support up to 180 lb/LF @ 25' spans
We will need 36 of these per bay = Total of 468

B1 | Treat joist loads as uniform loads
160 lb/LF x 25' = 4000 lb/4' = 1000 lb/LF ⇒ Use a 104SLH22 which supports 1034 lb/LF @ 141' spans (our span is only 140')
We will need a total of 14 of these.

Concrete Columns:

Axial Load:

40 lb/SF X 70' x 25' = 70,000 lb/column.

This would use a 10" x 10" square concrete column with 4-#5's.

We would need 28 of these columns

STANDARD ASD LOAD TABLE
OPEN WEB STEEL JOISTS, K-SERIES

Based on a 50 ksi Maximum Yield Strength
Adopted by the Steel Joist Institute November 4, 1985
Revised to November 10, 2003 - Effective March 01, 2005

The black figures in the following table give the TOTAL safe uniformly distributed load-carrying capacities, in pounds per linear foot, of **ASD K-Series** Steel Joists. The weight of DEAD loads, including the joists, must be deducted to determine the LIVE load-carrying capacities of the joists. Sloped parallel-chord joists shall use span as defined by the length along the slope.

The figures shown in **RED** in this load table are the nominal LIVE loads per linear foot of joist which will produce an approximate deflection of 1/360 of the span. LIVE loads which will produce a deflection of 1/240 of the span may be obtained by multiplying the figures in **RED** by 1.5. In no case shall the TOTAL load capacity of the joists be exceeded.

The approximate joist weights per linear foot shown in these tables do not include accessories.

The approximate moment of inertia of the joist, in inches^4 is:

$I = 26.767(W_{LL})(L^2)(10^{-3})$, where W_{LL} = **RED** figure in the Load Table and L = (Span - 0.33) in feet.

For the proper handling of concentrated and/or varying loads, see Section 6.1 in the Code of Standard Practice for Steel Joists and Joist Girders.

Where the joist span exceeds the unshaded area of the Load Table, the row of bridging nearest the mid span shall be diagonal bridging with bolted connections at the chords and intersections.

ASD

STANDARD LOAD TABLE FOR OPEN WEB STEEL JOISTS, K-SERIES
Based on a 50 ksi Maximum Yield Strength - Loads Shown in Pounds per Linear Foot (plf)


Joist Designation	8K1	10K1	12K1	12K3	12K5	14K1	14K3	14K4	14K5	16K3	16K5	16K4	16K6	16K5	18K7	18K6
Depth (in.)	8	10	12	12	12	14	14	14	14	16	16	16	16	16	18	18
Approx. Wt. (lbs./ft.)	5.1	5.0	5.0	5.7	7.1	5.5	6.0	6.7	7.7	5.5	6.3	7.0	7.5	8.1	8.6	10.0
Span (ft.)																
7	550															
8	550															
9	550															
10	550	550														
11	538	550														
12	444	550	550	550	550											
13	377	479	550	550	550											
14	324	412	550	550	550	550	550	550	550							
15	281	358	550	543	550	611	550	550	550							
16	246	313	549	476	550	448	550	550	550	550	550	550	550	550	550	550
17		277	485	420	550	396	495	550	550	512	550	550	550	550	550	550
18		248	434	374	537	352	441	530	550	456	530	550	550	550	550	550
19		221	388	335	481	315	395	475	550	408	475	547	550	550	550	550
20		199	349	302	433	284	355	428	535	368	428	493	550	550	550	550
21			316	273	392	257	322	385	478	333	371	447	508	548	550	550
22			288	249	357	234	293	350	432	303	337	405	461	498	550	550
23			261	227	326	214	268	320	396	277	308	371	418	455	507	550
24			239	208	298	196	245	293	363	254	283	340	384	418	465	505
25						180	225	270	334	234	260	313	353	384	428	514
26						166	208	249	308	216	240	289	326	355	395	474
27						154	193	231	285	200	223	268	302	329	366	439
28						143	179	215	265	186	207	249	281	306	341	409
29						133	167	200	247	173	193	232	262	285	317	382
30										161	180	216	244	266	296	355
31										151	169	203	229	249	277	332
32										142	158	190	214	233	260	311

VULCRAFT LOAD TABLE
SUPER LONGSPAN STEEL JOISTS, SLH-SERIES


Based on a 50 ksi Maximum Yield Strength


ASD

Joist Designation	Approx. Wt. In Lbs. per Linear Ft. (Joists Only)	Depth In Inches	Std. Load* In Lbs. Between	CLEAR SPAN IN FEET**															
			96-128	129	132	135	138	141	144	147	150	155	160	165	170	175	180	185	190
96SLH17	52	96	70,000	540	517	495	474	456	438	421	405	380	357	335	316	298	281	266	252
				389	363	339	318	298	280	263	247	224	204	186	170	156	143	132	122
96SLH18	59	96	78,800	606	583	559	535	513	493	475	457	430	405	381	360	340	322	305	289
				443	413	385	362	340	319	300	282	256	232	212	194	178	163	150	139
96SLH19	66	96	94,200	727	697	667	639	611	585	561	539	505	474	445	419	396	373	353	334
				502	469	439	410	385	361	340	320	290	264	241	220	202	186	171	158
96SLH20	74	96	105,000	824	789	754	722	691	662	635	610	571	536	504	475	448	423	400	378
				569	531	495	465	436	409	386	362	329	299	272	249	229	210	193	178
96SLH21	90	96	133,000	1027	982	940	900	864	829	797	766	719	675	635	598	564	533	504	477
				696	652	613	571	535	503	473	445	404	367	335	306	281	258	238	220
96SLH22	102	96	149,000	1150	1108	1067	1029	991	957	921	888	832	782	736	694	656	620	587	556
				811	757	708	663	622	584	549	517	469	426	389	355	326	300	276	255
			104-137	138	141	144	147	150	155	160	165	170	175	180	185	190	195	200	205
104SLH18	59	104	76,800	664	632	612	499	472	444	418	398	374	354	335	318	302	287	273	260
				426	400	375	353	332	301	274	250	229	209	192	177	164	152	140	130
104SLH19	67	104	93,400	674	647	622	599	574	539	507	479	452	427	404	383	364	346	325	312
				484	458	435	401	377	347	311	284	260	238	218	201	186	173	160	148
104SLH20	75	104	105,000	764	739	714	688	661	621	583	548	516	487	460	435	413	391	371	353
				548	519	493	469	447	387	358	331	308	287	268	251	235	221	208	197
104SLH21	90	104	132,000	956	917	881	847	813	763	718	677	639	604	573	541	514	488	464	441
				678	644	613	583	555	476	438	395	361	331	305	280	259	240	222	206
104SLH22	104	104	148,000	1073	1034	989	956	904	883	830	783	738	696	660	626	594	564	536	511
				785	736	689	648	610	553	503	459	420	386	353	326	301	278	258	240
104SLH23	128	104	163,000	1161	1141	1096	1052	1009	945	887	834	785	741	700	662	626	596	565	537
				819	769	721	679	638	578	526	480	439	403	370	341	315	291	270	250
			112-146	147	150	155	160	165	170	175	180	185	190	195	200	205	210	215	220
112LSLH19	97	112	91,900	623	600	564	530	500	472	446	424	402	382	362	345	329	314	300	286
				466	438	398	362	330	302	276	255	234	216	200	186	172	160	149	140
112SLH20	78	112	104,000	710	688	649	610	575	543	514	488	463	440	417	398	379	361	345	330
				538	497	450	410	374	342	312	288	266	246	227	210	195	181	169	156
112SLH21	91	112	131,000	891	858	805	757	713	673	637	603	572	543	516	491	468	446	426	407
				650	612	553	504	460	421	386	355	327	301	278	258	240	224	208	195
112SLH22	104	112	147,000	999	967	913	871	824	778	736	697	661	628	596	568	541	516	492	470
				756	711	644	586	535	489	449	412	380	350	324	301	279	260	242	226
112SLH23	110	112	162,000	1102	1067	1012	959	901	848	800	756	716	679	644	612	582	554	528	504
				790	744	674	613	560	512	469	431	397	367	340	316	293	272	253	236
112SLH24	131	112	192,000	1304	1263	1199	1139	1074	1014	959	909	862	819	778	741	706	673	642	613
				957	901	817	743	678	620	569	523	481	444	411	381	354	329	307	287
			102-164	165	170	175	180	185	190	195	200	205	210	215	220	230	235	240	
120SLH20	77	120	96,000	597	564	532	505	479	456	434	414	395	378	359	344	329	315	302	290
				430	393	361	332	306	282	261	242	225	209	195	182	170	159	149	140
120SLH21	92	120	123,000	748	706	667	632	599	570	542	516	492	469	449	428	410	392	376	360
				530	485	444	409	378	347	321	298	277	259	240	224	209	196	184	173
120SLH22	104	120	141,000	956	915	770	729	692	658	626	596	568	542	517	495	473	453	434	416
				618	564	516	475	439	404	374	347	322	300	279	261	244	228	214	201
120SLH23	111	120	159,000	943	898	848	804	763	725	690	657	626	596	569	545	513	496	475	456
				644	590	541	497	458	423	391	363	338	315	292	272	255	238	224	210
120SLH24	132	120	185,000	1117	1062	1003	950	902	858	816	777	741	706	675	645	617	591	566	543
				781	715	655	606	555	512	474	440	406	380	354	330	309	289	271	255
120SLH25	152	120	212,000	1291	1218	1152	1092	1036	984	936	891	850	811	775	741	709	678	650	622
				915	837	768	706	650	600	555	515	478	445	415	387	362	339	318	299



Natatorium Structural System Costs





03 23 Stressing Tendons

03 23 05 – Prestressing Tendons

03 23 05.50 Prestressing Steel

			Crew	Daily Output	Labor-Hours	Unit	Material	2019 Bare Costs Labor	Equipment	Total	Total Incl O&P
1050	45 kip	G	G3	420.00	.076	Lb.	1.12	.62	.02	1.76	2.39
1200	Ungrouted strand, 50' span, 100 kip	G	G4	1275	.025	"	.67	1.13	.02	1.82	2.55
1250	300 kip	G	"	1475	.022	"	.62	.98	.02	1.62	2.30
1400	500' span, 150 kip	G	"	1950	.021	"	.57	.96	.02	1.55	2.27
1450	300 kip	G	"	1950	.019	"	.62	.87	.02	1.51	2.13
1600	250' span, 300 kip	G	"	1200	.027	"	.62	1.24	.02	1.88	2.67
1650	300 kip	G	"	1700	.019	"	.62	.86	.02	1.50	2.07
1800	Ungrouted strand, 50' span, 42 kip	G	"	1400	.023	"	.67	1.05	.02	1.74	2.46
1850	148 kip	G	"	1700	.013	"	.78	.60	.02	1.40	1.96
2000	75' span, 42 kip	G	"	1800	.013	"	.78	.60	.02	1.40	1.96
2050	148 kip	G	"	2200	.015	"	.78	.69	.02	1.49	2.09
2200	Ungrouted single strand, 100' slab, 25 kip	G	"	1300	.027	"	.67	1.20	.02	1.89	2.67
2250	35 kip	G	"	1475	.024	"	.62	1.08	.02	1.72	2.43

03 24 Fibrous Reinforcing

03 24 05 – Reinforcing Fibers

03 24 05.30 Synthetic Fibers

0010	SYNTHETIC FIBERS										
0100	Synthetic fibers, add to concrete					Lb.	4.43			4.43	4.87
0110	1-1/2 lb. per C.Y.					C.Y.	5.85			5.85	6.45

03 24 05.70 Steel Fibers


0010	STEEL FIBERS										
0050	Steel fibers, add to concrete	G				Lb.	.70			.70	.77
0155	25 lb. per C.Y.	G				C.Y.	17.50			17.50	19.25
0160	50 lb. per C.Y.	G					35			35	38.50
0170	75 lb. per C.Y.	G					54			54	59.50
0180	100 lb. per C.Y.	G					70			70	77

03 30 Cast-In-Place Concrete

03 30 53 – Miscellaneous Cast-In-Place Concrete

03 30 53.40 Concrete In Place

0010	CONCRETE IN PLACE										
0020	Including forms (4 uses), reinforcing steel, concrete, placement,										
0050	and finishing unless otherwise indicated										
0300	Beams, 5 kip per L.F., 10' span		G1446	15.62	12.804	C.Y.	400	515	49	964	1,300
0350	25' span		"	19.55	13.702	"	430	550	51	1,031	1,400
0500	Chimney foundations, industrial, minimum		G1445	22.22	9.374	"	165	380	35	580	790
0510	Maximum		"	28.57	4.724	"	200	191	18	409	555
0700	Columns, square, 12" x 12", minimum reinforcing		G1446	11.56	16.609	"	400	670	64	1,134	1,550
0720	Average reinforcing		"	10.13	19.743	"	725	790	75.50	1,589.50	2,200
0740	Maximum reinforcing		"	8.08	23.148	"	1,150	930	89.50	2,169.50	2,950
0800	16" x 16", minimum reinforcing		"	6.22	32.030	"	915	1,300	123	2,338	3,175
0820	Average reinforcing		"	12.57	19.561	"	625	790	75.50	1,490.50	2,050
0840	Maximum reinforcing		"	10.25	23.512	"	1,025	950	91	2,066	2,800
0900	24" x 24", minimum reinforcing		"	10.66	22.514	"	575	910	87.50	1,572.50	2,150
0920	Average reinforcing		"	13.71	17.943	"	675	725	69.50	1,469.50	2,000
0940	Maximum reinforcing		"	10.67	23.051	"	1,050	930	89.50	2,069.50	2,800
1000	36" x 36", minimum reinforcing		"	10.67	23.051	"	575	930	89.50	1,594.50	2,175
1020	Average reinforcing		"	13.33	18.456	"	675	745	71.50	1,491.50	2,025



05 21 Steel Joist Framing


05 21 16 – Longspan Steel Joist Framing

05 21 16.50 Longspan Joists		Crew	Daily Output	Labor-Hours	Unit	2005 Bare Costs Material	Labor	Equipment	Total	Total Incl O&P
2400	28LH06, 16 lb/LF	G	E-7	1800	.044	LF	18.05	.96	1.12	20.13	24.50
2420	28LH11, 25 lb/LF	G		1800	.044		25	.96	1.12	27.08	31.50
2440	32LH08, 17 lb/LF	G		1800	.044		19.30	.96	1.12	21.38	25.50
2460	32LH13, 30 lb/LF	G		1800	.044		34	.96	1.12	36.08	42
2480	36LH09, 21 lb/LF	G		1800	.044		25.50	.96	1.12	27.58	32.50
2500	36LH14, 36 lb/LF	G		1800	.044		43.50	.96	1.12	45.58	52
2520	40LH11, 25 lb/LF	G		2200	.036		28.50	1.60	.91	31.01	36
2540	40LH16, 42 lb/LF	G		2200	.036		43.50	1.60	.91	46.01	53.50
2560	44LH11, 22 lb/LF	G		2200	.036		25	1.60	.91	27.51	31.50
2580	44LH16, 42 lb/LF	G		2200	.036		47.50	1.60	.91	50.01	58
2600	48LH11, 22 lb/LF	G		2200	.036		25	1.60	.91	27.51	31.50
2620	48LH16, 42 lb/LF	G	↓	2200	.036	↓	47.50	1.60	.91	50.01	58
2630	For less than 40 ton job,										
2632	For 30 to 39 tons, add						10%				
2634	20 to 29 tons, add						30%				
2636	10 to 19 tons, add						50%				
2637	5 to 9 tons, add						90%	25%			
2638	1 to 4 tons, add						75%	50%			
2639	Less than 1 ton, add						100%	100%			
2642	For extra long spans, add							50%			

05 21 19 – Open Web Steel Joist Framing

05 21 19.10 Open Web Joists

	OPEN WEB JOISTS										
2070	Add for extra over metals										
2070	Cranes, 40 ton int. capac. bridge, cycle to 30', shop prime, minimum	G	E-7	15	5.333	Ton	1,525	245	184	2,164	2,550
2080	Average	G		12	6.667		2,050	245	167	2,611	3,050
2090	Maximum	G		9	8.889	↓	2,450	340	223	3,013	3,525
2130	881, 5.1 lb/LF	G		2200	.067	LF	5.25	2.34	1.67	9.26	12.65
2140	1061, 5.3 lb/LF	G		2200	.067		5.10	2.34	1.67	9.11	12.45
2160	1265, 5.7 lb/LF	G		2200	.055		5.80	2.85	1.34	9.99	13.55
2180	1469, 5.0 lb/LF	G		2200	.055		5.10	2.85	1.34	9.29	12.70
2200	1668, 5.8 lb/LF	G		1800	.044		5.40	.96	1.12	7.48	9.65
2220	1668, 5.1 lb/LF	G		1800	.044		5.25	.96	1.12	7.33	9.50
2240	1885, 7.7 lb/LF	G		2200	.040		7.60	1.76	.75	10.11	12.80
2260	689, 10.2 lb/LF	G		2200	.040	↓	9.40	1.76		11.16	13.65
2280	Span 30' to 50', minimum	G		17	4.706	Ton	1,775	205	115	2,095	2,450
2290	Average	G		17	4.706		2,000	205	115	2,320	2,700
2300	Maximum	G		12	5	↓	2,175	355	221	2,751	3,250
2320	2285, 8.2 lb/LF	G		2000	.060	LF	8.20	1.76	1	10.96	13.15
2340	2285, 10.8 lb/LF	G		2000	.060		9.80	1.76	1	12.56	15.05
2360	2285, 8.8 lb/LF	G		2000	.060		9.80	1.76	1	12.56	15.05
2380	2549, 11.5 lb/LF	G		2000	.060		11.30	1.76	1	14.06	16.80
2400	2446, 9.7 lb/LF	G		2200	.036		9.70	.80	.57	11.07	13.15
2420	2413, 13.1 lb/LF	G		2200	.036		11.90	.80	.57	13.27	15.80
2440	2669, 10.6 lb/LF	G		2200	.036		10.60	.80	.57	11.97	14.25
2460	2613, 12.8 lb/LF	G		2200	.036		11.80	.80	.57	13.17	15.70
2480	2883, 12.1 lb/LF	G		2400	.033		12.30	.73	.52	13.55	16.15
2500	2883, 17.1 lb/LF	G		2400	.033		17.30	.73	.52	18.55	22.50
2520	3083, 13.3 lb/LF	G		2400	.033		13.20	.73	.52	14.45	17.25
2540	3083, 17.6 lb/LF	G	↓	2400	.033	↓	17.80	.73	.52	19.05	23
2560	For less than 40 ton job,										
2562	For 30 to 39 tons, add						10%				



05 21 Steel Joist Framing

05 21 13 – Deep Longspan Steel Joist Framing

05 21 13.50 Deep Longspan Joists


		Crew	Daily Output	Labor Hours	Unit	Material	2009 Bare Costs Labor	Equipment	Total	Total Incl O&P
3220	600H12, 29 LB/LF	G	E-7	2000	.040	LF	35	1.75	1	37.75	42.5
3230	600H12, 54 LB/LF	G		2000	.040		62.50	1.75	1	65.25	72.5
3240	600H12, 37 LB/LF	G		2000	.040		47	1.75	.91	49.66	55
3250	640H12, 57 LB/LF	G		2200	.036		62.50	1.60	.91	65.01	72.5
3260	680H12, 37 LB/LF	G		2200	.036		47.50	1.60	.91	49.01	54
3280	680H12, 61 LB/LF	G		2200	.036		73.50	1.60	.91	76.01	84.5
3420	720H14, 43 LB/LF	G		2200	.036		49.50	1.60	.91	52.01	58
3430	720H15, 70 LB/LF	G		2200	.036		84	1.60	.91	86.51	96.5
3500	For less than 40 ton jobs										
3502	5 to 20 tons, add						10%				
3504	20 to 25 tons, add						5%				
3506	10 to 15 tons, add						10%				
3507	5 to 9 tons, add						15%	25%			
3508	1 to 4 tons, add						75%	50%			
3509	Less than 1 ton, add						100%	100%			
4000	SLH series, 40-ton jobs, school cost pricing, shop primer										
4020	Spans to 200' (shown in 3 pieces), minimum	G	E-7	16	.5	Ton	2,200	221	126	2,547	2,950
4040	Average	G		13	6.154		3,475	271	155	3,901	4,525
4050	Maximum	G		11	7.273		3,950	320	183	4,453	5,175
4200	90SLH15, 43 lb/LF	G		1800	.053	LF	49.50	2.33	1.34	53.17	60
4220	90SLH20, 75 lb/LF	G		1800	.053		92.50	2.33	1.34	96.17	108
4240	105SLH16, 46 lb/LF	G		1800	.053		57	2.33	1.34	60.67	68
4260	105SLH21, 89 lb/LF	G		1800	.053		110	2.33	1.34	113.67	127
4280	105SLH24, 97 lb/LF	G		1800	.053		120	2.33	1.34	123.67	138
4300	105SLH28, 102 lb/LF	G		1800	.053		126	2.33	1.34	129.67	145
4320	104SLH15, 59 lb/LF	G		1800	.044		73	1.95	1.12	76.07	85.5
4340	104SLH20, 109 LB/LF	G		1800	.044		135	1.95	1.12	138.07	153
4360	112SLH15, 67 lb/LF	G		1800	.044		82.50	1.95	1.12	85.58	95.5
4380	112SLH24, 131 LB/LF	G		1800	.044		162	1.95	1.12	165.08	185
4400	120SLH20, 77 lb/LF	G		1800	.044		95	1.95	1.12	98.08	110
4420	120SLH28, 152 LB/LF	G		1800	.044		188	1.95	1.12	191.08	214
5000	For less than 40 ton jobs										
5002	For 50 to 99 tons, add						10%				
5004	20 to 49 tons, add						20%				
5006	10 to 19 tons, add						50%				
5007	5 to 9 tons, add						50%	25%			
5008	1 to 4 tons, add						75%	50%			
5009	Less than 1 ton, add						100%	100%			

05 21 16 – Longspan Steel Joist Framing

05 21 16.50 Longspan Joists

2010	LONGSPAN JOISTS									
2030	LH series, 40-ton jobs, school cost pricing, shop primer									
2035	Made from recycled materials									
2040	Spans to 96', minimum	G	E-7	16	.5	Ton	2,090	221	126	2,437	2,825
2060	Average	G		13	6.154		3,250	271	155	3,676	4,225
2080	Maximum	G		11	7.273		3,675	320	183	4,178	4,825
2200	18LH04, 12 LB/LF	G		1400	.057	LF	15.55	2.52	1.44	19.51	23
2220	18LH05, 19 LB/LF	G		1400	.057		21.50	2.52	1.44	25.46	29.50
2240	30LH04, 12 LB/LF	G		1400	.057		15.55	2.52	1.44	19.51	23
2260	30LH05, 19 LB/LF	G		1400	.057		21.50	2.52	1.44	25.46	29.50
2280	24LH05, 15 LB/LF	G		1400	.057		14.70	2.52	1.44	18.66	22
2300	24LH10, 28 LB/LF	G		1400	.057		25	2.52	1.44	29.46	34.50

120



05 31 Steel Decking

05 31 23 – Steel Roof Decking

05 31 23.50 Roof Decking

			Crew	Daily Output	Labor Hours	Unit	Material	2009 Bare Costs: Labor	Equipment	Total	Total Incl O&P
2200	20-500 squares	G				S.F.					
2400	501-2000 squares	G									
2600	20 gauge, over 2000 squares	G									
2650	2,501-5000 squares	G									
2700	Over 5,000 squares	G									
2900	18 gauge, under 501 squares	G									
2950	501-2000 squares	G									
3000	Over 2000 squares	G									
3050	16 gauge, under 501 squares	G									
3200	501-2000 squares	G									
3300	Over 2000 squares	G									
3350	For painted finish, add to unpainted price	G									
3360	For galvanized finish, add to unpainted price	G									

05 31 33 – Steel Form Decking

05 31 33.50 Form Decking

			Crew	Daily Output	Labor Hours	Unit	Material	2009 Bare Costs: Labor	Equipment	Total	Total Incl O&P
0010	**FORM DECKING**										
0015	Made from recycled materials										
4100	Steel form, galv, 28 gauge, 9/16" deep, uncoated	G	L-4	4000	.008	S.F.	1.72	.26	.28	2.26	2.67
4200	Galvanized	G		4000	.008		1.97	.26	.28	2.51	2.95
4220	24 gauge, 1" deep, painted	G		3800	.008		1.87	.27	.28	2.42	2.86
4240	Galvanized	G		3800	.008		2.27	.27	.28	2.82	3.32
4300	24 gauge, 1-5/16" deep, painted	G		3800	.008		1.95	.27	.28	2.50	2.94
4400	Galvanized	G		3800	.008		2.34	.27	.28	2.89	3.39
4500	22 gauge, 1-5/8" deep, painted	G		3700	.008		2.50	.28	.29	3.07	3.61
4600	Galvanized	G		3700	.008		2.85	.28	.29	3.42	3.99
4700	22 gauge, 2" deep, painted	G		3600	.009		3.08	.30	.31	3.69	4.30
4800	Galvanized	G		3600	.009		3.22	.30	.31	3.83	4.46
7000	Smooth cellular deck for form, 9" wide with 2 bands, galv										
7100	18 gauge	G	L-4	360	.022	L.F.	5.85	.84	.57	7.26	8.70
7200	16 gauge	G		360	.022		7.75	.84	.57	9.16	10.85

05 35 Raceway Decking Assemblies

05 35 13 – Steel Cellular Decking


05 35 13.50 Cellular Decking

			Crew	Daily Output	Labor Hours	Unit	Material	2009 Bare Costs: Labor	Equipment	Total	Total Incl O&P
0010	**CELLULAR DECKING**										
0015	Made from recycled materials										
0200	Cellular units, galv, 2" deep, 22/22 gauge, over 15 squares	G	E-4	1450	.027	S.F.	10.20	.99	.09	11.28	13.10
0250	18/20 gauge	G		1430	.028		11.60	1.02	.09	12.71	14.70
0300	16/18 gauge	G		1390	.029		11.95	1.04	.10	13.09	15.20
0320	14/16 gauge	G		1360	.029		14.20	1.06	.10	15.36	17.60
0340	12/14 gauge	G		1330	.030		15.85	1.09	.10	17.04	19.45
0400	3" deep, galvanized, 20/20 gauge	G		1375	.029		13.45	1.03	.10	14.58	16.85
0500	18/20 gauge	G		1350	.030		13.80	1.07	.10	14.97	17.30
0600	16/18 gauge	G		1290	.031		13.95	1.12	.10	15.17	17.60
0700	14/16 gauge	G		1230	.033		15.25	1.17	.11	16.53	19.15
0800	12/14 gauge	G		1150	.038		16.65	1.26	.12	18.03	20.90
1000	4-7/8" deep, galvanized, 22/18 gauge	G		1170	.027		15.70	1.01	.12	16.83	19.29
1100	20/18 gauge	G		1040	.031		15.60	1.39	.13	17.12	19.75
1200	18/18 gauge	G		980	.033		17.55	1.48	.14	19.17	22
1300	16/16 gauge	G		935	.034		19.15	1.55	.14	20.84	24

124

Modified Schedule – Without Glulam in Natatorium

	Natatorium - Pool Floor Steel Placement	5 days	Mon 6/15/09	Fri 6/19/09	114	Pool
	Natatorium - Pool Floor Concrete Placement	1 day?	Mon 6/22/09	Mon 6/22/09	115	Pool
	Natatorium - Pool Walls Rough-In	10 days	Tue 6/23/09	Mon 7/6/09	116	Pool
	Natatorium - Pool Walls Steel Placement	15 days	Tue 7/7/09	Mon 7/27/09	117	Pool
	Natatorium - Pool Walls Concrete Placement	2 days	Thu 7/30/09	Fri 7/31/09	118	Pool
	Natatorium - Drill Piers	10 days	Tue 6/2/09	Mon 6/15/09	15	Concrete
	Natatorium - Form and Reinforce Spread Footings	11 days	Mon 8/3/09	Mon 8/17/09	119	Concrete
	Natatorium - MEP Underground	10 days	Mon 8/3/09	Fri 8/14/09	119	MEP
	Natatorium - Pour Slab-On Grade	2 days	Tue 8/18/09	Wed 8/19/09	122,121	Concrete
	Natatorium - Form, Reinforce, and Pour Columns	5 days	Thu 8/20/09	Wed 8/26/09	123	Concrete
	Natatorium - Steel Erection	20 days	Thu 8/20/09	Wed 9/16/09	23,123	Concrete
	Natatorium - Top Out	0 days	Wed 9/16/09	Wed 9/16/09	125,124	All
	Natatorium - CMU North Wall	5 days	Thu 9/17/09	Wed 9/23/09	126	Masonry
	Natatorium - CMU East Wall	5 days	Thu 9/24/09	Wed 9/30/09	127	Masonry
	Natatorium - CMU South Wall	5 days	Thu 10/1/09	Wed 10/7/09	128	Masonry
	Natatorium - Face North Wall	5 days	Thu 10/8/09	Wed 10/14/09	129	Masonry
	Natatorium - Brick East Wall	5 days	Thu 10/15/09	Wed 10/21/09	130	Masonry
	Natatorium - Brick South Wall	5 days	Thu 10/22/09	Wed 10/28/09	131	Masonry
	Natatorium - Roof Decking	15 days	Mon 4/20/09	Fri 5/8/09		Steel
	Natatorium - Windows	20 days	Thu 10/29/09	Wed 11/25/09	132	Windows
	Natatorium - Dry-In	0 days	Wed 11/25/09	Wed 11/25/09	134	All
	Natatorium - Pool Gutter System	20 days	Mon 5/11/09	Fri 6/5/09	133	Pool
	Natatorium - Standing Seam Roofing System	20 days	Mon 5/11/09	Fri 6/5/09	133	Roofing
	Natatorium - Overhead Rough-in	10 days	Thu 11/26/09	Wed 12/9/09	135	MEP
	Natatorium - Interior Framing	10 days	Thu 12/10/09	Wed 12/23/09	138	Drywall



Appendix 7 – Analysis #2 (Mechanical System) References

Mechanical System Cost Calculations

Mechanical System Pricing

Cooling Tower:

Material: $30,171 (supplier's price)

Labor: $2650 (RS Means 2008, pg. 374)

Additional Pumps + Piping:

Labor + Material: $94.50/Ton x 276 Tons = $26,082 (RS Means 2008, pg. 374)

Chiller (WC):

Material: 276 Tons x $340/Ton = $93,840 (Supplier's Price)

Labor: $11,700 (RS Means 2008, pg. 373)


Add'l Structural Support For Cooling Towers:

Labor + Material: $15,557 (estimate from MEC)

Total Cost for New Design: $180,000

Previous Mechanical System Cost: $228,523 (from Mechanical Contractor)

Initial Savings of: $48,523



23 64 Packaged Water Chillers

23 64 26 – Rotary-Screw Water Chillers

23 64 26.10 Rotary-Screw Type Water Chillers	Crew	Daily Output	Labor-Hours	Unit	Material	2008 Bare Costs Labor	Equipment	Total	Total Incl O&P
0010 330 ton	Q-7	.72	27.5	Ea.	168,500	2,400		170,900	199,000
0020 Packaged unit, water cooled, no ind. tower									
0070 80 ton	Q-7	.54	29.8	Ea.	38,000	10,300		48,300	57,500
0080 100 ton		.44	33.0		46,700	10,300		57,000	68,000
0090 150 ton		.33	34.0		64,500	10,900		75,400	87,000
0100 200 ton		.33	35.1		73,600	11,600		85,200	97,000
0120 250 ton		.32	36.0		87,000	11,400		98,400	107,000
0130 300 ton	Q-8	.42	38.6		95,000	12,000		107,000	122,500
0150 350 ton	"	.33	39.4	"	104,000	12,400		116,400	133,500
1400 Water cooled, tower not included									
1500 135 ton cooling, screw compressors	Q-7	.44	23.5	Ea.	55,000	10,600		65,600	76,500
1520 50 ton cooling, screw compressors		.33	24.0		63,500	10,800		74,300	86,000
1540 400 ton cooling, screw compressors		.33	24.0		86,500	11,200		97,700	113,500
1560 291 ton cooling, screw compressors	"	.32	25.0	"	97,500	11,700		109,200	119,500


23 64 33 – Direct Expansion Water Chillers

23 64 33.10 Direct Expansion Type Water Chillers									
0010 DIRECT EXPANSION TYPE WATER CHILLERS, With remote condenser									
0080 Direct expansion, shell and tube type, for built-up systems									
0100 1 ton	Q-5	2	8	Ea.	5,975	340		6,315	7,075
0120 5 ton		1.90	8.421		9,900	355		10,255	11,400
0140 10 ton		1.70	9.412		13,300	400		13,700	15,100
0160 20 ton		1.50	10.667		14,000	450		14,450	16,100
0180 30 ton		1	16		17,900	680		18,580	20,700
0200 50 ton	"	.90	17.778		25,000	755		25,755	28,700
0220 100 ton	Q-6	.80	26.667	"	51,000	1,175		52,175	58,000

23 65 Cooling Towers

23 65 13 – Forced-Draft Cooling Towers

23 65 13.10 Forced-Draft Type Cooling Towers									
0010 FORCED-DRAFT TYPE COOLING TOWERS, Prefabricated units 03300-310									
0070 Galvanized steel									
0080 Factory built, crossflow									
0100 Vertical shaft drive, 60 ton	Q-6	50	.267	Ton	96	17.75		113.75	133
0140 100 ton		100	.240		76	15.95		91.95	109
0200 125 ton		105	.229		64	15.20		79.20	96
0240 150 ton		120	.200		55.50	13.30		68.80	85.50
0260 200 ton	"	130	.185	"	55	12		67	82.50
1020 For higher capacities, use multiples									
1040 Factory built, double flow									
1060 Vertical, gear drive, 150 ton	Q-6	95	.168	Ton	102	11.20		113.20	135
1080 200 ton		120	.133		73	8.85		81.85	98.50
1100 300 ton		150	.107		60.50	7.10		67.60	81.50
1120 400 ton		180	.089		59.50	5.90		65.40	78.50
1140 500 ton	"	190	.084	"	57	5.55		62.55	75
1160 Base mount, centrifugal pump									
1180 50 ton	Q-6	2.28	10.526	Ea.	13,400	465		13,865	15,500
1200 75 ton		1.52	15.789		13,500	695		14,195	15,900
1220 100 ton	"	1.52	15.789		15,900	865		16,765	18,800
1240 125 ton	Q-7	1.81	24.862		19,600	1,100		20,700	23,300
1260 200 ton	"	.92	34.783	"	24,000	1,550		25,550	29,100



23 65 Cooling Towers

23 65 13 – Forced-Draft Cooling Towers

23 65 13.10 Forced-Draft Type Cooling Towers	Crew	Daily Output	Labor-Hours	Unit	2008 Bare Costs Material	Labor	Equipment	Total	Total Incl O&P
2556 250 ton	Q-7	.62	49.23	ea.	29,000	2,200		31,200	35,200
2560 300 ton		.54	59.259		33,400	2,650		36,050	40,700
2564 350 ton		.47	68.085		37,700	3,020		40,720	45,700
2568 400 ton		.41	78.049		39,300	3,500		42,800	48,500
2572 450 ton		.38	88.764		47,200	3,950		51,150	58,000
2576 500 ton		.32	100		50,600	4,500		55,100	62,500
2580 550 ton		.30	107		54,500	4,825		59,325	67,000
2584 600 ton		.27	117		57,000	5,275		62,275	70,500
2588 650 ton		.25	127		63,500	5,725		69,225	78,000
2592 700 ton		.23	137		74,500	6,175		80,675	91,500
2596 750 ton		.22	145		79,500	6,600		86,100	97,500
2600 800 ton		.21	152		86,500	6,850		93,350	105,500
2604 850 ton		.20	156		91,500	7,050		98,550	111,500
2608 900 ton		.20	160		97,000	7,250		104,250	117,500
2612 950 ton		.19	170		102,500	7,650		110,150	124,000
2616 1000 ton	↓	.18	180	↓	105,500	8,125		113,625	129,000
2700 Add for induced draft									
2710 50 ton	Q-6	2.28	10.526	Ea.	9,000	465		9,465	10,600
2720 75 ton		1.52	15.789		10,800	695		11,495	12,900
2724 100 ton	↓	1.22	19.672		11,200	865		12,065	13,600
2728 125 ton	Q-7	1.81	24.527		13,800	1,100		14,900	16,900
2732 200 ton		1.32	36.218		23,400	1,625		25,025	28,400
2736 250 ton		.85	49.53		26,400	2,225		28,625	32,500
2740 300 ton		.74	56.259		30,900	2,525		33,425	37,900
2744 350 ton		.67	68.085		33,000	3,050		36,050	40,900
2748 400 ton		.61	78.049		37,800	3,500		41,300	46,900
2752 450 ton		.56	88.154		42,000	3,950		45,950	52,000
2756 500 ton		.52	100		44,000	4,500		48,500	55,000
2760 550 ton		.50	107		49,800	4,825		54,625	62,500
2764 600 ton		.47	117		52,500	5,275		57,775	66,000
2768 650 ton		.45	127		57,500	5,725		63,225	71,500
2772 700 ton		.43	137		65,500	6,175		71,675	81,500
2776 750 ton		.42	145		68,000	6,500		74,500	84,500
2780 800 ton		.41	152		71,000	6,850		77,850	88,500
2784 850 ton		.40	156		71,500	7,050		78,550	89,000
2788 900 ton		.40	160		74,000	7,250		81,250	92,000
2792 950 ton		.39	170		78,000	7,650		85,650	97,000
2796 1000 ton	↓	.38	180	↓	89,500	8,125		97,625	110,500
3000 For other capacities, use multiples									
3500 For pumps and piping, add	Q-6	38	.632	unit	48	29		76	94.50
4000 For blowdown system, add					250	250			
4100 Cooling water chemical tests	Q-5	3	5.333	Ea.	272	226		498	645
5000 Fiberglass									
5010 Crossflow									
5100 50 ton	Q-6	1.50	16	Ea.	3,450	705		4,155	4,850
5120 125 ton		.99	24.242		7,050	1,075		8,125	9,375
5140 300 ton		.43	55.814		16,500	2,450		18,950	21,800
5160 500 ton		.22	109		29,500	4,900		34,400	39,500
5180 1000 ton	↓	.15	160	↓	51,000	7,025		58,025	66,500
6000 Stainless steel									
6010 Induced draft, counterflow, isolation, bolted									
6100 57 ton	Q-6	1.50	16	Ea.	9,675	705		10,380	11,700
6120 81 ton	↓	.99	24.242	↓	13,900	1,075		14,975	16,900

Water Cooled Chiller Spec Sheet

Southland - Houston Chiller Study
RTHD-1

General

Capacity:
276.00 tons

Compressor configuration:
C2

Efficiency:
0.667 kW/ton

IPLV:
0.512 kW/ton

NPLV:
0.549 kW/ton

Evaporator

Evap configuration:
D3

Evap pressure drop:
5.50 ft H2O

Evap leaving temp:
42.00 F

Evap fouling factor:
0.00010 hr-sq ft-deg F/Btu

Evap flow rate:
470.90 gpm

Evap fluid concentration:
0.00 %

Minimum evap flow rate:
324.00 gpm

Evap fluid freeze point:
32.00 F

Evap entering temp:
56.00 F

Evap fluid type:
Water

Number of evap passes:
3 Pass

Condenser

Cond configuration:
E3

Cond fouling factor:
0.00025 hr-sq ft-deg F/Btu

Cond entering temp:
85.00 F

Cond fluid concentration:
0.00 %

Cond flow rate:
792.80 gpm

Cond tube type:
Enhanced Fin - Copper

Cond leaving temp:
95.00 F

Cond water side pressure:
150psi/10.5Bar Condenser Water Pressure

Number of cond passes:
2 Pass

Cond fluid type:
Water

Cond pressure drop:
11.10 ft H2O

Electrical

Unit voltage:
460/60/3

Max overcurrent protection:
600.00 A

Starter type:
Wye-delta

Starter expected inrush:
469.00 A

Unit power:
184.00 kW

Motor locked rotor amps:
1453.00 A

Run load amps:
266.50 A

Max RLA (for starter sizing):
364

Min circuit ampacity:
333.10 A

Miscellaneous

Full load sound pressure (ARI Condition):
83 dBA

Shipping weight:
14002.0 lb

Refrigerant charge (HFC-134a):
490.0 lb

ARI certification:
ARI certified

Oil cooler:
Without Oil Cooler

Rated capacity (ARI):
307.30 tons

ARI certified selection:
Yes

Distribution channel:
United States

Operating weight:
15044.0 lb

Pressure vessel code:
ASME Pressure Vessel Code

Test

Performance test options:
No Performance Test

Factory tolerance test:
No performance test

Cooling Tower Spec Sheet

Chesapeake Systems

7400 Coca-Cola Drive
Hanover, MD 21076
Phone:-443-561-1600 Fax:-443-561-1601
Web Address: www.chesapeakesys.com

Offer of Sale

Reference No. 13643

To: Matt Smiddy
Attn:

Date: 2/19/2010

Business Fax:

Job Name: **Penn State Project**
Job Engineer:

Thank you for requesting a quotation on the following equipment:

Danfoss Variable Frequency Drive(s)
Evapco Cooling Tower(s)

We are pleased to submit our offer based on the conditions indicated.

[CT-1] Quantity (1) Evapco Cooling Tower(s), Model AT-19-99

276 Ton Induced Draft Counterflow Cooling Tower. CTI Certified to Cool 828 GPM of Water from 95 F to 85 F @ 77 F Entering Wet Bulb Temperature - Qty (1) 20 HP Fan (460/3/60)

Base Price Includes:

- "EVAPCOAT" G-235 Galvanized Construction (Casing & Panels & Basin)
- Stainless Steel Strainers
- PVC EVAPAK Fill & Drift Eliminators (Drift Rate Not To Exceed 0.001% of Recirculation Flow)
- "Sight Tight" PVC Air Inlet Louvers & Screen Design (Prevents Light From Entering the Basin)
- 100% Corrosion Free Water Distribution System
- Solid Backed/Multi-Grooved "Power Band" Belt Drive
- Pillow Block Bearings With a Minimum L-10 Life of 75,000 Hours
- Cast Aluminum Drive Sheaves
- External Motor/Belt Drive Adjustment
- Extended Lubrication Lines
- Internal Working Platform for Service of Water Distribution System and Fan/Motor Drive System
- EVAPCO Thermal Performance Guarantee
- CTI Certified
- IBC Compliant
- 5-Year Motor & Drive Parts Warranty

Note: Motors are Shipped Loose for Field Mounting by Others on 8.5'Wide Units
Note: Unless Noted Otherwise All Accessories Ship Loose for Field Installation

Energy Cost Calculations

Cooling Tower/Chiller Energy Cost

W-C Chiller: $0.667 \frac{kW}{Ton}$ (Supplier) $\times 276\ Ton = 184\ kW$

Cooling Tower: Assume COP of 4 $\Rightarrow \frac{kW}{Ton} = \frac{12}{COP \times 3.412} = \frac{12}{4 \times 3.412} = 0.879 \frac{kW}{Ton}$

$0.879 \frac{kW}{Ton} \times 276\ Ton = 243\ kW$

Total Energy Usage of New System: 427 kW

Total Energy Usage of Old System:

2 A-C Chillers @ $1.3 \frac{kW}{Ton}$ ea $= 2.6 \frac{kW}{Ton} \times 276\ Tons = 718\ kW$

Save: 291 kW

Energy Costs: ~10¢/kW·h in Houston, Tx

So each day, $291 \times 24 \times 0.1 =$ $698/Day Savings

Month: $20,707

Year: $248,488

Appendix 8 – Analysis #3 (Delivery Methods) References

Response from General Contractor's Survey

The purpose of this survey is to investigate the interaction of the Pearland Recreation Center and Natatorium project team. This survey has been designed to capture the general contractor's viewpoint.

1) If you were to redo the project, would you change the delivery method? If so, what would you change it to and why? If not, what were the advantages of the Design-Bid-Build delivery method chosen? ***A: The architect & I have spoken often that this should have been a CM @ Risk type contract. That is because of the difficult design features, there have been many small changes to the contract that would be easier to resole if the CM @ Risk method had been used. Typically the CMR anticipates these challenges and has allowances to care for that.***

2) How frequently did you interact with the designers? ***A: We meet a minimum of once a week with the architect, and he often visits the site once or twice more during the week to consult with the superintendents.***

3) How frequently did you interact with the owners? ***A: We meet every other week at a progress meeting.***

4) What was the most common method of communication with designers? ***A: Telephone conversations, with email a close second.***

5) What was the most common method of communication with the owners? ***A: Telephone.***

6) What are the *main* criteria that were used to select the subcontractors and suppliers? Would you modify any of these criteria if you were to do it over again? ***A: As a hard bid, the primary selection criteria were price, with ability to perform the project second. It is hard to modify this criterion when the project is a hard bid. Selection of a better qualified sub, but at a higher cost might make our bid higher, and thus we would not be the low bidder.***

7) What types of contracts were held between the subcontractors/suppliers and general contractor? ***A: I have attached a sample contract.***

8) What language would you add/remove/change in these contracts if you were to do it over again? ***A: We re content with our current contract.***

9) What language was specifically effective? ***A: We find the duration language, and that the days allowed for various work to run concurrent helps the superintendent to push the project.***

10) How frequently were Owner-Architect-Contractor meetings held? Was this frequency adequate? ***A: Meetings are held every other week. This is adequate.***

11) How often would the architect and/or owner representative visit the construction site? ***A: Owner at least once every other week, and sometimes once a week. The architect is on site a minimum of once a week, and the architect has a construction representative on site every day for at least ½ day.***

Response from Owner's Survey

The purpose of this survey is to investigate the interaction of the Pearland Recreation Center and Natatorium project team. This survey has been designed to capture the owner's viewpoint.

1) Why was the Design-Bid-Build delivery method chosen?
This is the typical Method chosen by the City for Complex projects such as this.

2) If you were to redo the project, would you change the delivery method? If so, why? If not, what were the advantages of the Design-Bid-Build delivery method chosen?
No, this method is the best. CMAR & DB would not have served the City well for this type of project. Simple big box stores and office buildings might lend themselves to other methods — see pg 2 #2

3) What *main* criteria were used to select the designer?
-- Familiarity with similar projects
-- Familiarity with key funding, Stakeholder & User
- Understanding of concept of project & working on municipal projects

4) What would you change in these criteria if you were to do it over again?
None

5) What *main* criteria were used to select the general contractor?
Competitive Sealed proposal criteria, as attached, from the Instructions to Bidders (pg 1-3)

6) What would you change in these criteria if you were to do it over again?
None.

7) Did the contract with the contractor and designer contain any specific language requiring interaction between the two parties? If so, what?
There is no contract btwn contractor & designer. The contract is with the owner & specified coordination with the owner on certain items, as well as with other agencies, see attached Sec 0800

8) What language would you add/remove/change in the contract if you were to do it over again? None.

9) How frequently were Owner-Architect-Contractor meetings held? Was this frequency adequate? Meetings once and Every 2 weeks, or more. Frequently if certain circumstances required

10) How often would the architect and/or owner representative visit the construction site?
Owner's rep is on site daily, as specified in the consultant contract (architect also provides construction management oversight.)

#2 The DBB method allows the designer & owner to review all aspects of the proposed facility before construction starts. The user group & stakeholders have more time to provide input at all stages of design.

13. Opening of Bid Proposals

Bid Proposals will be opened and (unless obviously non-responsive) read aloud publicly. An abstract of the amounts of the base Bid Proposals and major alternates (if any) will be made available to Bidders after the opening of Bid Proposals. Bid Proposals, in their entirety, shall be open for public inspection after the contract is awarded, with the exception of any trade secrets or confidential information contained therein, provided Bidder has expressly identified any specific information contained therein as being trade secrets or confidential information.

14. Bid Proposals to Remain Subject to Acceptance

All Bid Proposals will remain subject to acceptance for sixty (60) days after the day of the Bid Proposal opening, but Owner may, in its sole discretion, release any Bid Proposal and return the bid security prior to that date.

15. Award of Contract

15.1 Owner reserves the right to reject any and all Bid Proposals, to waive any and all informalities not involving price, time or changes in the Work and to negotiate contract terms with the Successful Bidder. Owner may reject a bid as non-responsive if: 1) Bidder fails to provide required Bid Security; 2) Bidder improperly or illegibly completes or fails to complete all information required by the Bidding Documents; 3) Bidder fails to sign the Bid Proposal or improperly signs the Bid Proposal; 4) Bidder qualifies its Bid Proposal; 5) Bidder tardily or otherwise improperly submits its Bid Proposal; 6) Bidder fails to submit the Qualifications of Bidder as required under section 3 of these Instructions to Bidders; or 7) Bid Proposal is otherwise non-responsive. In determining the best value for the Owner, and in determining to whom to award a contract, Owner may consider: 1) purchase price; 2) reputation of the Bidder and Bidder's goods or services; 3) quality of Bidder's goods or services; 4) extent to which the goods or services meet the Owner's needs; 5) Bidder's past relationship with the Owner; 6) impact on the ability of Owner to comply with laws and rules relating to contracting with historically underutilized businesses and nonprofit organizations employing persons with disabilities; 7) total long-term cost to Owner to acquire Bidder's goods or services; 8) the Qualifications of Bidder; and 9) any other relevant criteria specifically listed in the Bidding Documents. Discrepancies in the multiplication of units of Work and unit prices will be resolved in favor of the unit prices. Discrepancies between the indicated sum of any column of figures and the correct sum thereof will be resolved in favor of the correct sum.

15.1.1 **For exact Selection Criteria, Refer to "Exhibit A", Sheet 00200-Exhibit A**

15.2 In evaluating Bid Proposals, Owner will consider the Qualifications of the Bidders, whether or not the Bid Proposals comply with the prescribed requirements, and such alternates, unit prices and other data, as may be requested in the Bid Proposal form or prior to the Notice of Award.

pg 2

Exhibit "A"

SELECTION CRITERIA

DETERMINATION OF SUCCESSFUL RESPONDENT AND AWARD OF CONTRACT

A. In determining the Selected Offeror, the Owner will evaluate the information derived from the Offeror's (Contractor's) Qualification Statement required herein, the information submitted on the Proposal Form, and other selection criteria including, but not be limited to the following:

	Criteria	Source	Scoring Procedure	Score	Factor	Total
1.	Base Proposal	Proposal Form	Contractor to submit their Competitive Sealed Proposals on the forms included in the Specification Manual, Alternates proposed and Mark-up for Changes. Low Price – 45 pts. For Subsequent Proposer's, the low Proposed price shall be divided by the Subsequent Proposer's price to get a percentage (factor) that is multiplied by the score to get the total.	45	1	45
2.	Contractor's Reputation	AIA 305	References in Houston Area are asked to rate the contractor. a. Reference responses from Project Owners and A/E's on similar projects. b. Reference questions on budget, schedule, reporting/ communications and responsiveness. c. Record of Claims Incidences and Litigation experiences over the past five years. d. Reputation of Change Orders. Responses are scored as follows: Excellent – 10 pts; Very Good – 8 pts; Average – 5 pts; Fair – 2 pts; Poor – 0 pts Points from multiple references are averaged	10	1	10
3.	Experience	AIA 305 (type and size)	Count number of similar projects in the Houston area that fall within a +/- 25% range of the project budget. a. Past experience on projects of similar scope, scale, complexity and type. b. References in the Houston area if contractor brings appropriate resources (personnel & equipment) to assure project completion by contract target end dates. Contractor earns one point for each project up to a maximum of 10 points.	10	1	10
4.	Maintenance of Schedule	References	References in Houston Area are asked whether or not the schedule was met on their project. Responses are scored as follows: Completed ahead of schedule overcoming uncontrollable circumstances = 5 pts; Completed ahead of schedule = 4 pts Completed on schedule = 3 pts; Completed less than two weeks behind schedule = 1 pt; Completed more than two weeks behind schedule = 0 pts Points from multiple references are averaged	5	1	5

pg 3

5.	*Project Team*	*Proposal Information* (resumes)	*Resumes for Project Manager and Superintendent* will each be examined and points given to the team for the following: Time in business (for each individual): 10+ yrs – 4 pts; 8-9 yrs – 3 pts; 5-7 yrs – 2 pts; 3-4 yrs – 1 pt, and less than 2 yrs = 0 pts. Number of similar projects completed (for each individual): 4— 4 pts; 3 – 3 pts; 2 – 2 pts; 1 – 1 pt; 0 – 0 pts. Time with the Company (for each individual) 5+ yrs – 5 pts; 4 yrs – 4 pts; 3 yrs – 3 pts; 2 yrs – 2 pts; 1 yr – 1 pt. and less than 1 yrs = 0 pts. Number of projects completed as a team: 5+ = 5 pts; 4 = 4 pts; 3 = 3 pts; 2 = 2 pts; 1 = 1 pt; and less than – 0 pts.	35	0.2778	10
6.	*Approach*	*Proposal Information*	*The Project Plan or Approach proposed.* a. **Quality and clarity of proposer's workplan including** schedule, logistics/phasing plan, understanding of the work and sensitivity to ongoing operations in the Community. Responses are scored as follows: Excellent – 5 pts; Very Good – 4 pts; Average = 3 pts; Fair = 2 pts; Poor – 0 pts.	5	1	5
7.	*Proposed Subcontractors*	*Proposal Information*	*The Major Subcontractors proposed by Contractor.* a. **Quality of Major Subcontractors listed.** b. **Experience of Major Subcontractors with Projects** of similar scope and size. c. **References in Houston ISD Subcontractors bring** appropriate resources (personnel and equipment) to ensure project completion by contract target end dates. Responses are scored as follows: Excellent – 5 pts; Very Good = 4 pts; Average – 3 pts; Fair – 2 pts; Poor = 0 pts. Points from multiple references are averaged.	5	1	5
8.	*Safety Rating*	*AIA 305*	*Contractors to provide the Owner with their* Experience Modifier Rate (EMR). Those with EMR of 0.50 or less = 5 pts; EMR of 0.51 – 0.85 – 4 pts; EMR of 0.86 – 0.99 – 3 pts; EMR greater than 1.00 = 0 pts. Maximum of 5 points.	5	1	5
9.	*Warranty*	*References*	*References in Houston Area are asked to rate the contractor.* Responses are scored as follows: Excellent = 5 pts; Very Good = 4 pts; Average = 3 pts; Fair = 2 pts; Poor = 0 pts. Points from multiple references are averaged.	5	1	5
					Total Possible Score	100

00200 – Exhibit A

#7

Section 00800

SPECIAL CONDITIONS OF AGREEMENT

The following Special Conditions modify the General Conditions, Document 00700. Where a portion of the General Conditions is modified or deleted by these Special Conditions, the unaltered portions of the General Conditions shall remain in effect.

1.01 Add the following paragraph to the end of Article 1.01:

The OWNER'S representative on the project is: Andrea Brinkley, 3501 E. Orange, Phone 281 652-1797.

4.23 Add the following Notes at the end of Article 4.23:

1. Contractor shall note that any work in the roadways (Bailey Road and Veterans Drive) is limited to the hours between 9:00 AM and 2:00 PM.

2. Contractor shall contact and coordinate work in the roadways with the School Hours and Bus times with the Pearland Independent School District.

3. Contractor shall notify BDD #4 (Brazoria Drainage District) prior to any drainage work to be performed in either Springfield Ditch to the North of the property and Cowarts Creek to the south of the property.

4. Contractor shall contact the City of Pearland prior to any work on the new Sanitary Sewer line along Veterans Drive and for any storm sewer outfalls or tie-ins to existing drainage.

ACADEMIC VITA of Matt Smiddy

Matt Smiddy
137 H. Alley Apt. 201
State College, PA 16801
msmiddy5055@gmail.com

Education: Bachelor of Architectural Engineering, Penn State University, Spring 2010
Bachelor of Arts in Economics, Penn State University, Spring 2010
Honors in Architectural Engineering
Thesis Title: Pearland Recreation Center and Natatorium
Thesis Supervisor: James A. Faust

Related Experience:

Intern, ExxonMobil Development Company (Houston, TX) 05/09 – 08/09
- Re-wrote the Construction Coordination Procedure Pro-Forma for use in all project contracts.
- Assisted in expediting first oil on the Banyu Urip ($2 B) project in Indonesia
- Created an outline for a Temporary Facilities Global Practice

Intern, The Alexander Building Company (State College, PA) 12/08-5/09
- Led the implementation of Building Information modeling into the company.
- Used a 3-story office building as a prototype

Intern, Facchina-McGaughan LLC. (Miami, FL) 05/07 – 08/07, 05/08 – 08/08
- Assisted in management of construction of concert hall designed by Frank Gehry - $100M
- Assisted in management of construction of 43-Story Condominium project - $130M

Intern, The Whiting-Turner Contracting Company (Miami, FL) 05/06 – 08/06
- Assisted in management of construction of 33-Story Condominium project - $90M
- Bid out 4 scope of works
- Oversaw the project's quality control program, submitting 10 QC reports/week

Research Assistant, Pennsylvania Transportation Institute 03/08 – 12/08
- Assisted in testing bearing capacities of asphalt cores for PENDOT

Teaching Assistant, Penn State University 09/08 - Present
- Coordinated exam and homework grading for 75 students in Environmental Economics and 75 students in Material Science for Civil Engineers courses

BIM Execution Guide Project 09/08 – 12/08
- Created a publicly available guide for using BIM for cost estimating.
- Performed a BIM case study on the New World Symphony Concert Hall

Awards:

Engineer-In-Training
Golden Key International Honour Society
Schreyer Honors College Scholar
2009 Hettema Leadership Award Recipient
Tau Beta Pi Engineering Honor Society
Phi Kappa Phi Honor Society Member
Phi Alpha Epsilon Honor Society Member

Presentations/Activities:

President and Web Master, Student Chapter of Partnership for Achieving Construction Excellence
Member, 2005-2006 Penn State Men's Varsity Swim Team
Member and Web Master, Penn State Water Polo Team
President and Web Master, Penn State Club Swim Team
Family Member Chair, Robert J. Smiddy Memorial Scholarship Award Committee
Volunteer, Special Olympics
Envoy, Penn State Engineering Coop & Internship Program